

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

APPLICATION FOR PERMIT TO DRILL, DEEPEN

1a. TYPE OF WORK DRILL <input type="checkbox"/> DEEPEN <input checked="" type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. ML-16532	
1b. TYPE OF WELL OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> OTHER <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME N/A	
2. NAME OF OPERATOR Newfield Production Company		7. UNIT AGREEMENT NAME N/A	
3. ADDRESS AND TELEPHONE NUMBER: Route #3 Box 3630, Myton, UT 84052 Phone: (435) 646-3721		8. FARM OR LEASE NAME N/A	
4. LOCATION OF WELL (FOOTAGE) At Surface NW/NE 497' FNL 1982' FEL 40,036 730 At proposed Producing Zone 57436 88 4319 944 -110,121 298		9. WELL NO. State #2A-16-9-16	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE* Approximately 20.4 miles southwest of Myton, UT		10. FIELD AND POOL OR WILDCAT Monument Butte	
15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any) Approx. 497' f/lse line and NA' f/unit line		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NW/NE Sec. 16, T9S, R16E	
16. NO. OF ACRES IN LEASE 640.00		12. County Duchesne	
17. NO. OF ACRES ASSIGNED TO THIS WELL 40		13. STATE UT	
18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR ON THIS LEASE, FT. Approximately 1341'		19. PROPOSED DEPTH 6500'	
20. ROTARY OR CABLE TOOLS Rotary		21. ELEVATIONS (Show whether DF, RT, GR, etc.) 5809' GL	
22. APPROX. DATE WORK WILL START* 1st Quarter 2008		23. PROPOSED CASING AND CEMENTING PROGRAM	
SIZE OF HOLE	SIZE OF CASING	WEIGHT/FOOT	SETTING DEPTH
12 1/4	8 5/8	24#	290'
7 7/8	5 1/2	15.5#	TD
		QUANTITY OF CEMENT	
		155 sx +/- 10%	
		275 sx lead followed by 450 sx tail	
		See Detail Below	

DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give date on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

***The actual cement volumes will be calculated off of the open hole logs, plus 15% excess:**

SURFACE PIPE - 155 sx Class G Cement +/- 10%, w/ 2% CaCl₂ & 1/4#/sk Cello-flake
Weight: 15.8 PPG YIELD: 1.17 Cu Ft/sk H₂O Req: 5 gal/sk

LONG STRING - Lead: Premium Lite II Cement + 3lbs/sk BA-90 + 3% KCl + .25 lbs/sk Cello Flake + 2 lbs/sk Kol Seal + 10% Bentonite + .5% Sodium Metasilicate
Weight: 11.0 PPG YIELD: 3.43 Cu Ft/sk H₂O Req: 21.04 gal/sk

Tail: 50-50 Poz-Class G Cement + 3% KCl + .25 lbs/sk Cello Flake + 2% Bentonite + .3% Sodium Metasilicate
Weight: 14.2 PPG YIELD: 1.59 Cu Ft/sk H₂O Req: 7.88 gal/sk

24. Name & Signature Mandie Crozier Title: Regulatory Specialist Date: 11/19/2007

(This space for State use only)

API Number Assigned: 43-013-33846

APPROVAL: _____

Approved by the
Utah Division of
Oil, Gas and Mining

*See Instructions On Reverse Side

Date: 02-25-08By: [Signature]


RECEIVED

NOV 29 2007

DIV. OF OIL, GAS & MINING


T9S, R16E, S.L.B.&M.

N89°50'W - 80.24 (G.L.O.)




NEWFIELD PRODUCTION COMPANY

WELL LOCATION, 9 MILE 2-16-9-16,
LOCATED AS SHOWN IN THE NW 1/4 NE
1/4 OF SECTION 16, T9S, R16E,
S.L.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST OF
MY KNOWLEDGE AND BELIEF. No. 189377



TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 10-11-07	SURVEYED BY: C.M.
DATE DRAWN: 11-01-07	DRAWN BY: F.T.M.
REVISED:	SCALE: 1" = 1000'

9 MILE 2-16-9-16
(Surface Location) NAD 83
LATITUDE = 40° 02' 12.17"
LONGITUDE = 110° 07' 18.94"

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV;
U.S.G.S. 7-1/2 min QUAD (MYTON SE)

NEWFIELD PRODUCTION COMPANY
STATE #2A-16-9-16
NW/NE SECTION 16, T9S, R16E
DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0 – 1700'
Green River	1700'
Wasatch	6500'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation 1700' – 6500' – Oil

4. **PROPOSED CASING PROGRAM:**

Surface Casing: 8-5/8" J-55 24# w/ST&C collars; set at 290' (New)

Production Casing: 5-1/2" J-55, 15.5# w/LT&C collars; set at TD (New or used, inspected).

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

A fresh water/polymer system will be utilized to drill the well. If necessary, to control formation fluids, the system will be weighted with the addition of bentonite gel, and if conditions warrant, barite. This fresh water system typically will contain Total Dissolved Solids (TDS) of less than 3000 PPM. Neither potassium chloride nor chromates will be utilized in the fluid system. The anticipated mud weight is 8.4 ppg and weighted as necessary for gas control.

AIR DRILLING

In the event that the proposed location is to be "Air Drilled", Newfield requests a variance to regulations requiring a straight run blowline. Newfield proposes that the flowline will contain two (2) 90-degree turns. Newfield also requests a variance to regulations requiring an automatic igniter or continuous pilot light on the blowline. Newfield requests authorization to ignite as needed, and the flowline at 80'.

Newfield Production Company requests that the spark arrest, exhaust, or water cooled exhaust be waived under the Special Drilling Operations of Onshore Order #2.

MUD PROGRAM

Surface – 3200’
3200’ – TD’

MUD TYPE

fresh water system
fresh water system

From surface to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCL substitute additive. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite. No chromate additives will be used in the mud system.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 290’ +/-, and a Compensated Neutron-Formation Density Log from TD to 3500’ +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

The anticipated maximum bottom hole pressure is 1800 psi. It is not anticipated that abnormal temperatures will be encountered; or that any other abnormal hazards such as H2S will be encountered in this area.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the first quarter of 2008, and take approximately seven (7) days from spud to rig release.

NEWFIELD PRODUCTION COMPANY
STATE #2A-16-9-16
NW/NE SECTION 16, T9S, R16E
DUCHESNE COUNTY, UTAH

THIRTEEN POINT SURFACE PROGRAM

1. **EXISTING ROADS**

See attached **Topographic Map "A"**

To reach Newfield Production Company well location site State #2A-16-9-16 located in the NW¼ NE¼ Section 16, T9S, R16E, S.L.B. & M., Duchesne County, Utah:

Proceed in a southwesterly direction out of Myton, Utah along Highway 40 approximately 1.4 miles to the junction of this highway and Utah State Highway 53; proceed southerly along Utah State Highway 53 approximately 1.7 miles to its junction with an existing road to the southwest; proceed southwesterly approximately 9.7 miles to its junction with an existing road to the southeast; proceed southeasterly approximately 0.3 miles to its junction with an existing road to the northeast; proceed northeasterly approximately 5.1 miles to its junction with an existing road to the southwest; proceed southwesterly approximately 1.8 miles to its junction with an existing road to the northwest; proceed in a northwesterly direction approximately 1.4 miles to its junction with the beginning of the proposed access road to the south; proceed southerly along the proposed access road approximately 840'; turn and continue in a southeasterly direction along the proposed access road approximately 1070' to the proposed well location.

The highways mentioned in the foregoing paragraph are bituminous surfaced roads to the point where Highway 216 exists to the South, thereafter the roads are constructed with existing materials and gravel. The highways are maintained by Utah State road crews. All other roads are maintained by County crews.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal.

2. **PLANNED ACCESS ROAD**

Approximately 1,910' of access road is proposed. See attached **Topographic Map "B"**.

The proposed access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%.

There will be no culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. **LOCATION OF EXISTING WELLS**

Refer to **EXHIBIT B**.

4. **LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted Desert Tan. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Fresh water purchased from the Johnson Water District will be used for drilling. A temporary poly pipeline may be used for water transportation from our existing supply line from Johnson Water District, or trucked from Newfield Production Company's injection facilities – **EXHIBIT A**.

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Bcluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

8. **ANCILLARY FACILITIES:**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT:**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. **PLANS FOR RESTORATION OF SURFACE:**

a) **Producing Location**

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) **Dry Hole Abandoned Location**

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP:** State of Utah

12. **OTHER ADDITIONAL INFORMATION:**

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

The Archaeological Cultural Resource Survey Report is attached. **Refer to Exhibit "D"**.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the State 2A-16-9-16, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the State 2A-16-9-16 Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office shall be notified upon site completion prior to moving on the drilling rig.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

Representative


Name: Dave Allred
Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that Newfield Production Company is considered to be the operator of well #2A-16-9-16, NW/NE Section 16, T9S, R16E, LEASE #ML-16532, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Hartford Accident #4471291.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.



11/19/07
Date


Mandie Crozier
Regulatory Specialist
Newfield Production Company

NEWFIELD PRODUCTION COMPANY

9 MILE 2-16-9-16

Section 16, T9S, R16E, S.L.B.&M.



SURVEYED BY: C.M.

DATE SURVEYED: 10-11-07

DRAWN BY: F.T.M.

DATE DRAWN: 11-01-07

SCALE: 1" = 50'

REVISED:





Tri State
 Land Surveying, Inc.

(435) 781-2501

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

NEWFIELD PRODUCTION COMPANY

CROSS SECTIONS 9 MILE 2-16-9-16



NOTE:
UNLESS OTHERWISE
NOTED ALL CUT/FILL
SLOPES ARE AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)



ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	3,600	3,600	Topsoil is not included in Pad Cut	0
PIT	640	0		640
TOTALS	4,240	3,600	1,060	640

SURVEYED BY: C.M.	DATE SURVEYED: 10-11-07
DRAWN BY: F.T.M.	DATE DRAWN: 11-01-07
SCALE: 1" = 50'	REVISED:

Tri State
Land Surveying, Inc.
(435) 781-2501
180 NORTH VERNAL AVE. VERNAL, UTAH 84078


NEWFIELD PRODUCTION COMPANY


TYPICAL RIG LAYOUT 9 MILE 2-16-9-16



SURVEYED BY: C.M.	DATE SURVEYED: 10-11-07
DRAWN BY: F.T.M.	DATE DRAWN: 11-01-07
SCALE: 1" = 50'	REVISED:

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078
(435) 781-2501





NEWFIELD
Exploration Company

9 Mile 2-16-9-16
SEC. 16, T9S, R16E, S.L.B.&M.



Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1 = 100,000
DRAWN BY: mw
DATE: 11-02-2007


Legend

Existing Road

Proposed Access

TOPOGRAPHIC MAP

"A"



NEWFIELD
Exploration Company

9 Mile 2-16-9-16
SEC. 16, T9S, R16E, S.L.B.&M.



Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078


SCALE: 1" = 2,000'
DRAWN BY: mw
DATE: 11-02-2007


Legend

Existing Road
 Proposed Access

TOPOGRAPHIC MAP

"B"





NEWFIELD
Exploration Company

9 Mile 2-16-9-16
SEC. 16, T9S, R16E, S.L.B.&M.







Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: mw
DATE: 11-02-2007


Legend


 Roads

 Proposed Gas Line

TOPOGRAPHIC MAP

"C"





Proposed Location
9 Mile 2-16

NEWFIELD
Exploration Company

9 Mile 2-16-9-16
SEC. 16, T9S, R16E, S.L.B.&M.



Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: mw
DATE: 11-02-2007

Legend

- Location
- One-Mile Radius

Exhibit "B"

2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 11/29/2007

API NO. ASSIGNED: 43-013-33846

WELL NAME: STATE 2A-16-9-16

OPERATOR: NEWFIELD PRODUCTION (N2695)

PHONE NUMBER: 435-646-3721

CONTACT: MANDIE CROZIER

PROPOSED LOCATION:

NWNE 16 090S 160E

SURFACE: 0497 FNL 1982 FEL

BOTTOM: 0497 FNL 1982 FEL

COUNTY: DUCHESNE

LATITUDE: 40.03673 LONGITUDE: -110.1213

UTM SURF EASTINGS: 574968 NORTHINGS: 4431994

FIELD NAME: MONUMENT BUTTE (105)

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	DLD	2/25/08
Geology		
Surface		

LEASE TYPE: 3 - State

LEASE NUMBER: ML-16532

SURFACE OWNER: 3 - State

PROPOSED FORMATION: GRRV

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[] Ind[] Sta[] Fee[]
(No. B001834)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. MUNICIPAL)
☒ RDCC Review (Y/N)
(Date:)
☒ Fee Surf Agreement (Y/N)
☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

___ R649-2-3.

Unit: _____

☒ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells

___ R649-3-3. Exception

___ Drilling Unit

Board Cause No: _____

Eff Date: _____

Siting: _____


___ R649-3-11. Directional Drill

COMMENTS:

Needs Permit (12-13-07)

STIPULATIONS:

*1- Spacing Strip
2- STATEMENT OF BASIS
3- Surface Csg Cont Strip*



OPERATOR: NEWFIELD PROD CO (N2695)

SEC: 16 T.9S R. 16E

FIELD: MONUMENT BUTTE (105)

COUNTY: DUCHESNE

SPACING: R649-3-2 / GENERAL SITING

Field Status

- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Wells Status

- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL
- DRILLING



OIL, GAS & MINING



PREPARED BY: DIANA MASON
DATE: 05-DECEMBER-2007

Application for Permit to Drill

Statement of Basis

1/14/2008

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Ownr	CBM
627	43-013-33846-00-00		OW	S	No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD		
Well Name	STATE 2A-16-9-16		Unit		
Field	MONUMENT BUTTE		Type of Work		
Location	NWNE 16 9S 16E S 497 FNL 1982 FEL GPS Coord (UTM) 574968E 4431994N				

Geologic Statement of Basis

Newfield proposes to set 290' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 2,800'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 16. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought high enough to cover the estimated base of the moderately saline ground water.

Brad Hill
APD Evaluator

1/8/2008
Date / Time

Surface Statement of Basis

The general area is approximately 20 miles southwest of Myton, Utah in the upper Castle Peak area. Castle Peak Draw runs in a northeasterly direction about 14 miles and joins Pariette Draw. Pariette Draw continues in a southeasterly direction about 6 miles and joins the Green River about 6 miles below Ouray Utah. Pariette Draw contains a perennial stream somewhat consisting of irrigation runoff and seepage. No streams springs or seeps occur in the area. An occasional pond constructed to store runoff for livestock or wildlife exists. Drainages are ephemeral only flowing during spring snowmelt or following intense summer rainstorms. Broad flats or rolling topography intersected by drainages with gentle to moderate side-slopes characterize the area. Access to the area from Myton, Utah is following State of Utah Hwy. 40 and Duchesne County and oilfield development roads a distance of 20.4 miles. Construction of 1070 feet of new road will be required.

The proposed State #2A-16-9-16 oil well location is in rolling terrain with the reserve pit planned on a rise or ridge to the south. The pad will extend north with fill toward a gentle swale. Care should be exercised so as not to deposit fill in the bottom of this swale. A Gentle swale also exists to the west. No diversions are needed. The selected site poses no apparent surface concerns and appears to be a good location for constructing a pad, drilling and operating a well. The area was covered with about 10 inches of snow during the evaluation. Both the surface and minerals are owned by SITLA.

Daniel Emmett representing the Utah Division of Wildlife Resources stated the area is classified as substantial value sage grouse brooding habitat and crucial yearlong antelope habitat. He ask Mr. Allred of Newfield and Mr. Davis of SITLA that they try to schedule construction and drilling around the critical period of March 1 to June 15th for sagegrouse brooding. No restrictions for the antelope were requested. No other wildlife are expected to be significantly affected. Mr. Emmett gave Mr. Allred of Newfield Production Company and Mr. Davis of SITLA a copy of his evaluation and also a seed mix recommendation to be used when the reserve pit and location are reclaimed.

Floyd Bartlett
Onsite Evaluator

12/13/2007
Date / Time

Application for Permit to Drill

Statement of Basis

1/14/2008

Utah Division of Oil, Gas and Mining

Page 2

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator NEWFIELD PRODUCTION COMPANY
Well Name STATE 2A-16-9-16
API Number 43-013-33846-0 **APD No** 627 **Field/Unit** MONUMENT BUTTE
Location: 1/4,1/4 NWNE **Sec** 16 **Tw** 9S **Rng** 16E 497 FNL 1982 FEL
GPS Coord (UTM) 574976 4432000 **Surface Owner**

Participants

Floyd Bartlett (DOGM), David Allred (Newfield Production Company), Cory Miller (Tri-State Land Surveying), Jim Davis (SITLA), Daniel Emmett (Utah Division of Wildlife Resources).

Regional/Local Setting & Topography

The general area is approximately 20 miles southwest of Myton, Utah in the upper Castle Peak area. Castle Peak Draw runs in a northeasterly direction about 14 miles and joins Pariette Draw. Pariette Draw continues in a southeasterly direction about 6 miles and joins the Green River about 6 miles below Ouray Utah. Pariette Draw contains a perennial stream somewhat consisting of irrigation runoff and seepage. No streams springs or seeps occur in the area. An occasional pond constructed to store runoff for livestock or wildlife exists. Drainages are ephemeral only flowing during spring snowmelt or following intense summer rainstorms. Broad flats or rolling topography intersected by drainages with gentle to moderate side-slopes characterize the area. Access to the area from Myton, Utah is following State of Utah Hwy. 40 and Duchesne County and oilfield development roads a distance of 20.4 miles. Construction of 1070 feet of new road will be required.

The proposed State #2A-16-9-16 oil well location is in rolling terrain with the reserve pit planned on a rise or ridge to the south. The pad will extend north with fill toward a gentle swale. Care should be exercised so as not to deposit fill in the bottom of this swale. A Gentle swale also exists to the west. No diversions are needed. The selected site poses no apparent surface concerns and appears to be a good location for constructing a pad, drilling and operating a well. The area was covered with about 10 inches of snow during the evaluation. Both the surface and minerals are owned by SITLA.

Surface Use Plan

Current Surface Use

Grazing
Recreational
Wildlife Habitat

New Road

Miles	Well Pad	Src Const Material	Surface Formation
0.25	Width 199 Length 290	Onsite	UNTA

Ancillary Facilities N

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetland N

Flora / Fauna

Area was covered with snow. Vegetation is a Deseret shrub type. Identified or expected vegetation consisted of black sagebrush, shadscale, greasewood, mustard weed, rabbit brush, horsebrush, broom snakeweed, and spring annuals.

Cattle, prairie dogs, antelope, small mammals and birds. Golden eagle have been sited in the general area.

Soil Type and Characteristics

Moderately deep sandy clay loam with some surface rock.

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diversion Required N

Berm Required? N

Erosion Sedimentation Control Required? N

Paleo Survey Run? N **Paleo Potential Observed?** N **Cultural Survey Run?** Y **Cultural Resources?** N

Reserve Pit**Site-Specific Factors****Site Ranking**

Distance to Groundwater (feet)	>200	0
Distance to Surface Water (feet)	>1000	0
Dist. Nearest Municipal Well (ft)	1320 to 5280	5
Distance to Other Wells (feet)	300 to 1320	10
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	<10	0
Affected Populations	<10	0
Presence Nearby Utility Conduits	Not Present	0

Final Score 30 1 **Sensitivity Level**

Characteristics / Requirements

A 40' x 80' x 8' deep reserve pit is planned in an area of cut on the southeast side of the location. A pit liner is required. Newfield commonly uses a 16-mil liner.

Closed Loop Mud Required? N **Liner Required?** Y **Liner Thickness** 16 **Pit Underlayment Required?** Y

Other Observations / Comments


ATV's used to reach site. Site under 10 inches of snow.

Floyd Bartlett
Evaluator

12/13/2007
Date / Time

2008-01 Newfield State 2A-10-9-16

Casing Schematic



BOPE REVIEW

Well Name	Newfield State 2A-16-9-16 API 43-013-33846
------------------	--

INPUT	
Well Name	Newfield State 2A-16-9-16 API 43-013-33846
Casing Size (")	String 1 8 5/8 String 2 5 1/2 String 3 String 4
Setting Depth (TVD)	290 6500
Previous Shoe Setting Depth (TVD)	0 290
Max Mud Weight (ppg)	8.4 8.4
BOPE Proposed (psi)	0 2000
Casing Internal Yield (psi)	2950 4810
Operators Max Anticipated Pressure (psi)	1800 5.3 ppg

#NAME?

Calculations	String 1	8 5/8 "
Max BHP [psi]	.052*Setting Depth*MW =	127
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	92
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	63
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth) =	63
Required Casing/BOPE Test Pressure	290	psi
*Max Pressure Allowed @ Previous Casing Shoe =	0	psi
		*Assumes 1psi/ft frac gradient
		BOPE Adequate For Drilling And Setting Casing at Depth?
		NO
		NO <i>due shallow depth</i>
		*Can Full Expected Pressure Be Held At Previous Shoe?
		NO

Calculations	String 2	5 1/2 "
Max BHP [psi]	.052*Setting Depth*MW =	2839
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	2059
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	1409
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth) =	1473
Required Casing/BOPE Test Pressure	2000	psi
*Max Pressure Allowed @ Previous Casing Shoe =	290	psi
		*Assumes 1psi/ft frac gradient
		BOPE Adequate For Drilling And Setting Casing at Depth?
		NO
		YES ✓
		*Can Full Expected Pressure Be Held At Previous Shoe?
		NO - <i>known area - expected pressure ± 1000 psi less - no known problems in 2.5 yrs.</i>

Well name:	2008-01 Newfield State 2A-16-9-16	
Operator:	Newfield Production Company	Project ID:
String type:	Surface	43-013-33846
Location:	Duchesne County	

Design parameters:
Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 81 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 290 ft

Cement top: 153 ft

Burst

Max anticipated surface pressure: 352 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 400 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 349 ft

Non-directional string.
Re subsequent strings:

Next setting depth: 6,500 ft
Next mud weight: 8.400 ppg
Next setting BHP: 2,836 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 400 ft
Injection pressure: 400 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	400	8.625	24.00	J-55	ST&C	400	400	7.972	143

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	174	1370	7.853	400	2950	7.38	8	244	29.10 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Minerals

Phone: 801-538-5357
FAX: 801-359-3940

Date: January 15, 2008
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 400 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

2008-01 Newfield State 2A-16-9-16Operator: **Newfield Production Company**String type: **Production**

Project ID:

43-013-33846Location: **Duchesne County****Design parameters:****Collapse**

Mud weight: 8.400 ppg

Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No

Surface temperature: 75 °F

Bottom hole temperature: 166 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 1,500 ft

Cement top: 103 ft

Burst

Max anticipated surface pressure: 1,406 psi

Internal gradient: 0.220 psi/ft

Calculated BHP 2,836 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.

Neutral point: 5,674 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	6500	5.5	15.50	J-55	LT&C	6500	6500	4.825	868.6
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	2836	4040	1.424	2836	4810	1.70	88	217	2.47 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & MineralsPhone: 801-538-5357
FAX: 801-359-3940Date: January 15, 2008
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 6500 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

From: Ed Bonner
To: Mason, Diana
Date: 1/8/2008 12:05 PM
Subject: Well Clearance

CC: Davis, Jim; Garrison, LaVonne; Hill, Brad; Jarvis, Dan

The following wells have been given cultural resources clearance by the Trust Lands Cultural Resources Group:

ConocoPhillips Company
Utah 29-574D (API 43 015 30735)

EOG Resources, Inc
CWU 956-32 (API 43 047 39515)

Kerr McGee Oil & Gas Onshore LP
NBU 1021-2N (API 43 047 38840)

Newfield Production Company
Wells Draw Fed C-5-9-16 (API 43 013 33753)
State 1A-16-9-16 (API 43 013 33845)
State 2A-16-9-16 (API 43 013 33846)
State 3-16-9-16 (API 43 013 33847)
State 4-16-9-16 (API 43 013 33848)
State 5-16-9-16 (API 43 013 33849)
State 6-16-9-16 (API 43 013 33850)
State 12-16-9-16 (API 43 013 33852)
State 13-16-9-16 (API 43 013 33853)
State 16-16-9-16 (API 43 013 33854)

Pioneer Natural Resources USA, Inc
Main Canyon State 12-16-15-23 (API 43 047 39695)
Main Canyon State 34-21-15-23 (API 43 047 39696)
Horse Point State 34-10-16-23 (API 43 019 31558)
Horse Point State 41-1-16-23 (API 43 019 31599)
Grand Canyon State 23-35-15.5-23 (API 43 019 31560)

If you have any questions regarding this matter please give me a call.



JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil Gas and Mining

JOHN R. BAZA
Division Director

February 25, 2008

Newfield Production Company
Rt. #3, Box 3630
Myton, UT 84052

Re: State 2A-16-9-16 Well, 497' FNL, 1982' FEL, NW NE, Sec. 16, T. 9 South, R. 16 East,
Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-33846.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Duchesne County Assessor
SITLA

Operator: Newfield Production Company
Well Name & Number State 2A-16-9-16
API Number: 43-013-33846
Lease: ML-16532

Location: NW NE Sec. 16 T. 9 South R. 16 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at: (801) 538-5338 office (801) 942-0871 home
- Carol Daniels at: (801) 538-5284 office
- Dustin Doucet at: (801) 538-5281 office (801) 733-0983 home

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
7. Surface casing shall be cemented to the surface.

RECEIVED

MAR 12 2008

FORM 9

DIV. OF OIL, GAS & MINING

STATE OF UTAH

DIVISION OF OIL, GAS, AND MINING

1. SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NO. ML-16532
Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells. Use "APPLICATION FOR PERMIT TO DRILL OR DEEPEN" form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBAL NAME N/A
OIL <input type="checkbox"/> GAS <input type="checkbox"/> WELL <input type="checkbox"/> WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		7. UNIT AGREEMENT NAME NA
2. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY		8. WELL NAME AND NUMBER STATE 216-9-16
3. ADDRESS AND TELEPHONE NUMBER Rt. 3 Box 3630, Myton Utah 84052 435-646-3721		9. API NUMBER 43-013-33846
4. LOCATION OF WELL Footages 497 FNL 1982 FEL QQ, SEC, T, R, M: NW/NE Section 16, T9S R16E		10. FIELD AND POOL, OR WILDCAT MONUMENT BUTTE
		COUNTY DUCHESNE STATE UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA	
NOTICE OF INTENT: (Submit in Duplicate) <input type="checkbox"/> ABANDON <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> REPAIR CASING <input type="checkbox"/> PULL OR ALTER CASING <input type="checkbox"/> CHANGE OF PLANS <input type="checkbox"/> RECOMPLETE <input type="checkbox"/> CONVERT TO INJECTION <input type="checkbox"/> REPERFORATE <input type="checkbox"/> FRACTURE TREAT OR ACIDIZE <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> MULTIPLE COMPLETION <input type="checkbox"/> WATER SHUT OFF <input checked="" type="checkbox"/> OTHER <u>APD Change</u>	SUBSEQUENT REPORT OF: (Submit Original Form Only) <input type="checkbox"/> ABANDON* <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> REPAIR CASING <input type="checkbox"/> PULL OR ALTER CASING <input type="checkbox"/> CHANGE OF PLANS <input type="checkbox"/> RECOMPLETE <input type="checkbox"/> CONVERT TO INJECTION <input type="checkbox"/> REPERFORATE <input type="checkbox"/> FRACTURE TREAT OR ACIDIZE <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> OTHER _____ DATE WORK COMPLETED _____ Report results of Multiple Completion and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form. *Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depth for all markers and zones pertinent to this work.

Newfeild Production requests the following changes be made the drilling program on the above mentioned approved APD.
Surface Casing will be set @ 290'.

13. NAME & SIGNATURE Mandie Crozier TITLE Regulatory Specialist DATE 3/7/2008
(This space for State use only)

4/94

* See Instructions On Reverse Side

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
DATE 3/14/08
BY: [Signature]

COPY SENT TO OPERATOR

Date: 3.19.2008Initials: KS

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR: **NEWFIELD PRODUCTION COMPANY**
ADDRESS: **RT. 3 BOX 3630**
MYTON, UT 84052

OPERATOR ACCT. NO. **N2895**

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	Q1	SC	TP	RG	COUNTY	SPUD DATE	EFFECTIVE DATE
A	99999	16767	4304739268	FEDERAL 14-24-9-17	SESW	24	9S	17E	Utah DUCHESNE	3/26/2008	4/3/08
WELL 1 COMMENTS: <i>GRUV</i>											
B	99999	12275	4304739680	CASTLE DRAW STATE S-2-9-17	NESE	2	9S	17E	Utah DUCHESNE	3/27/2008	4/3/08
WELL 2 COMMENTS: <i>GRUV</i> <i>BHL = NESE</i>											
A	99999	16768	4301333845	State 1A-16-9-16 STATE 1-16-9-16	NENE	16	9S	16E	Utah DUCHESNE	3/29/2008	4/3/08
WELL 3 COMMENTS: <i>GRUV</i>											
B	99999	14844	4304734938	FEDERAL 2-1-9-17	NWNE	1	9S	17E	Utah DUCHESNE	3/29/2008	4/3/08
WELL 4 COMMENTS: <i>GRUV</i> <i>Sundance Unit</i>											
A	99999	16769	4301333846	State 2A-16-9-16 FEDERAL 2-16-9-16	NWNE	16	9S	16E	Utah DUCHESNE	3/31/2008	4/3/08
WELL 5 COMMENTS: <i>GRUV</i>											
A	99999	16770	4304739266	FEDERAL 12-24-9-17	NWSW	24	9S	17E	Utah DUCHESNE	3/31/2008	4/3/08
WELL 6 COMMENTS: <i>GRUV</i>											

ACTION CODES (See instructions on back of form)
A - new entity for new well (single well only)
B - well to existing entity (group or unit well)
C - from one existing entity to another existing entity
D - well from one existing entity to a new entity
E - other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

RECEIVED
APR 02 2008
DIV. OF OIL, GAS & MINING

Signature *[Signature]* Jentri Park
Production Clerk
Date 01/02/08

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>	5. LEASE DESIGNATION AND SERIAL NUMBER: UTAH STATE ML-16532
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052	7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER 435.646.3721	8. WELL NAME and NUMBER: STATE 2A-16-9-16
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 497 FNL 1982 FEL	9. API NUMBER: 4301333846
OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: NWNE, 16, T9S, R16E	10. FIELD AND POOL, OR WILDCAT: MONUMENT BUTTE
	COUNTY: DUCHESNE
	STATE: UT

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will Do not use this form for wells or	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) NEWFIELD PRODUCTION COMPANY Date of work completion: 04/07/2008	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Spud Notice
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 3/31/08 MIRU Ross # 21. Spud well @ 9:30 am. Drill 325' of 12 1/4" hole with air mist. TIH W/ 7 Jt's 8 5/8" J-55 24 # csgn. Set @ 324.36' KB. On 4/03/08 cement with 160 sks of class "G" w/ 3% CaCL2 + 1/4# sk Cello- Flake Mixed @ 15.8 ppg > 1.17 cf/ sk yeild. Returned 3 bbls cement to pit. WOC.

<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will Do not use this form for wells or	NAME (PLEASE PRINT) Jim Smith	TITLE Drilling Foreman
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) NEWFIELD PRODUCTION COMPANY Date of work completion: 04/07/2008	SIGNATURE 	DATE 04/07/2008

(This space for State use only)

RECEIVED

APR 09 2008

DIV. OF OIL, GAS & MINING

NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8 CASING SET AT 324.36

LAST CASING 8 5/8" SET AT 324.36
 DATUM 12' KB
 DATUM TO CUT OFF CASING _____
 DATUM TO BRADENHEAD FLANGE _____
 TD DRILLER 320' LOGGER N/A
 HOLE SIZE 12 1/4

OPERATOR Newfield Production
 WELL State 2-16-9-16
 FIELD/PROSPECT Monument Butte
 CONTRACTOR & RIG # Ross # 21

LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH
		44.77' SH jt					
		WHI - 92 csg head			8rd	A	0.95
7	8 5/8"	Maverick ST&C csg	24#	J-55	8rd	A	312.51
		GUIDE shoe			8rd	A	0.9
CASING INVENTORY BAL.		FEET	JTS	TOTAL LENGTH OF STRING			314.36
TOTAL LENGTH OF STRING		314.36	7	LESS CUT OFF PIECE			2
LESS NON CSG. ITEMS		1.85		PLUS DATUM TO T/CUT OFF CSG			12
PLUS FULL JTS. LEFT OUT		0		CASING SET DEPTH			324.36

TOTAL	312.51	7	} COMPARE
TOTAL CSG. DEL. (W/O THRDS)	296.06	7	
TIMING	1ST STAGE		
BEGIN RUN CSG. Spud	3/31/2008	9:30 AM	GOOD CIRC THRU JOB yes
CSG. IN HOLE	3/31/2008	5:00 PM	Bbls CMT CIRC TO SURFACE 3
BEGIN CIRC	4/3/2008	8:10 AM	RECIPROCATED PIPE IN/A _____
BEGIN PUMP CMT	4/3/2008	8:20 AM	DID BACK PRES. VALVE HOLD ? N/A
BEGIN DSPL CMT	4/3/2008	8:40	BUMPED PLUG TO _____ 137 PSI
PLUG DOWN	4/3/2008	8:50 AM	

CEMENT USED	CEMENT COMPANY- B. J.
STAGE IN / SX	CEMENT TYPE & ADDITIVES
TOTAL LENGTH 160	Class "G" w/ 2% CaCL2 + 1/4#/sk Cello-Flake mixed @ 15.8 ppg 1.17 cf/sk yield
LESS NON	
PLUS PL	

CENTRALIZER & SCRATCHER PLACEMENT	SHOW MAKE & SPACING
Centralizers - Middle first, top second & third for 3	

COMPANY REPRESENTATIVE Ray Herrera DATE 4/3/2008

BEGIN PUMP

BEGIN USE

PLUG DOWN

CEMENT USED

STAGE IN / SX

LOGGING

LOGGING

RECEIVED
MAR 05 2008
DIV. OF OIL, GAS & MINING

STATE OF UTAH

DIVISION OF OIL, GAS, AND MINING

1. SUNDRY NOTICES AND REPORTS ON WELLS		5. LEASE DESIGNATION AND SERIAL NO. ML-16532
Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells. Use "APPLICATION FOR PERMIT TO DRILL OR DEEPEN" form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBAL NAME N/A
<input type="checkbox"/> OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER		7. UNIT AGREEMENT NAME NA
2. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY		8. WELL NAME and NUMBER STATE 2A-16-9-16
3. ADDRESS AND TELEPHONE NUMBER Rt. 3 Box 3630, Myton Utah 84052 435-646-3721		9. API NUMBER 43-013-33846
4. LOCATION OF WELL Footages 497 FNL 1982 FEL QQ, SEC, T, R, M: NW/NE Section 16, T9S R16E		10. FIELD AND POOL, OR WILDCAT MONUMENT BUTTE
		COUNTY DUCHESNE STATE UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA	
NOTICE OF INTENT: (Submit in Duplicate)	SUBSEQUENT REPORT OF: (Submit Original Form Only)
<input type="checkbox"/> ABANDON <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> REPAIR CASING <input type="checkbox"/> PULL OR ALTER CASING <input type="checkbox"/> CHANGE OF PLANS <input type="checkbox"/> RECOMPLETE <input type="checkbox"/> CONVERT TO INJECTION <input type="checkbox"/> REPERFORATE <input type="checkbox"/> FRACTURE TREAT OR ACIDIZE <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> MULTIPLE COMPLETION <input type="checkbox"/> WATER SHUT OFF <input checked="" type="checkbox"/> OTHER APD Change	<input type="checkbox"/> ABANDON* <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> REPAIR CASING <input type="checkbox"/> PULL OR ALTER CASING <input type="checkbox"/> CHANGE OF PLANS <input type="checkbox"/> RECOMPLETE <input type="checkbox"/> CONVERT TO INJECTION <input type="checkbox"/> REPERFORATE <input type="checkbox"/> FRACTURE TREAT OR ACIDIZE <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> OTHER _____ DATE WORK COMPLETED _____ Report results of Multiple Completion and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form. *Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depth for all markers and zones pertinent to this work.

Newfield Production requests the change the name of the above mentioned well to the State 2-16-9-16.

13. NAME & SIGNATURE Mandie Crozier TITLE Regulatory Specialist DATE 3/4/2008
Mandie Crozier

(This space for State use only)

14. RAC

15. 4/94

16. 1/97

17. 1/97

18. 1/97

Approved by the
Utah Division of
Oil, Gas and Mining

* See Instructions On Reverse Side

COPY SENT TO OPERATOR

Date: 5.1.2008

Initials: KS

Date: 04-29-08

By: [Signature]

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER: UTAH STATE ML-16532
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 497 FNL 1982 FEL		8. WELL NAME and NUMBER: STATE 16-9-16
OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: NWNE, 16, T9S, R16E		9. API NUMBER: 4301333846
		10. FIELD AND POOL, OR WILDCAT: MONUMENT BUTTE
		COUNTY: DUCHESNE
		STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will 	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/STOP) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLAIR <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: - Weekly Status Report
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 05/01/2008			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 4/24/08 Ratterson Rig # 52. Set all equipment. Pressure test 4/25/08 Kelly, TIW, Choke manifold, & Bop's to 2,000 psi. Test 8.625 csgn to 1,500 psi. Vernal BLM field, & Roosevelt DOGM office was notified of test. PU BHA and tag cement @ 280'. Drill out cement & shoe. Drill a 7.875 hole with fresh water to a depth of 5,810. Lay down drill string & BHA. Open hole log w/ Dig/SP/GR log's TD to surface. PU & TIH with Guide shoe, shoe jt, float collar, 141 jt's of 5.5 J-55, 15.5# csgn. Set @ 5815.67' / KB. Cement with 300 sks cement mixed @ 11.0 ppg & 3.43 yld. Then 400 sks cement mixed @ 14.4 ppg & 1.24 yld. With 36 bbls cement returned to pit. Nipple down Bop's. Drop slips @ 110,000 #'s tension. Release rig 8:00 AM 4/30/08.

NAME (PLEASE PRINT) Alvin Nielsen

TITLE Drilling Foreman

SIGNATURE

Alvin Nielsen

DATE 05/01/2008

(This space for State use only)

RECEIVED
MAY 05 2008
DIV. OF OIL, GAS & MINING

NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

5 1/2" CASING SET AT 5815.67

Flt cllr @ 5796.33

LAST CASING 8 5/8" SET AT 324'

OPERATOR Newfield Production Company

DATUM 12

WELL State 2A-16-9-16

DATUM TO CUT OFF CASING 12

FIELD/PROSPECT Monument Butte

DATUM TO BRADENHEAD FLANGE

CONTRACTOR & RIG # Patterson # 52

TD DRILLER 5810 LOGGI 5828

HOLE SIZE 7 7/8"

LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH	
		Landing Jt					14	
		Short jt @ 43684' (7.08')						
141	5 1/2"	ETC LT & C casing	15.5#	J-55	8rd	A	5797.58	
							0.6	
1	5 1/2"	ETC LT&C csg	15.5#	J-55	8rd	A	20.09	
		GUIDE shoe			8rd	A	0.65	
CASING INVENTORY BAL.		FEET	JTS	TOTAL LENGTH OF STRING LESS CUT OFF PIECE PLUS DATUM TO T/CUT OFF CSG CASING SET DEPTH } COMPARE				5817.67
TOTAL LENGTH OF STRING		5817.67	142					14
LESS NON CSG. ITEMS		15.25						12
PLUS FULL JTS. LEFT OUT		166.35	4					5815.67
TOTAL		5968.77	146					
TOTAL CSG. DEL. (W/O THRDS)		5968.77	146					
TIMING		1ST STAGE	2nd STAGE					
BEGIN RUN CSG.		4/29/2008	8:30 PM	GOOD CIRC THRU JOB YES				
CSG. IN HOLE		4/30/2008	1:00 AM	Bbls CMT CIRC TO SURFACE 36				
BEGIN CIRC		4/30/2008	1:00 AM	RECIPROCATED PIPE FOR THRU FT STROKE				
BEGIN PUMP CMT		4/30/2008	3:50 AM	DID BACK PRES. VALVE HOLD ? YES				
BEGIN DSPL. CMT		4/30/2008	4:50 AM	BUMPED PLUG TO 1860 PSI				
PLUG DOWN		4/30/2008	5:10 AM					
CEMENT USED				CEMENT COMPANY- B. J.				
STAGE	# SX			CEMENT TYPE & ADDITIVES				
1	300	Premlite II w/ 10% gel + 3 % KCL, 3#'s /sk CSE + 2# sk/kolseal + 1/2#'s/sk Cello Flake						
		mixed @ 11.0 ppg W / 3.43 cf/sk yield						
2	400	50/50 poz W/ 2% Gel + 3% KCL, .5%EC1,1/4# sk C.F. 2% gel. 3% SM mixed @ 14.4 ppg W/ 1.24 YLD						
CENTRALIZER & SCRATCHER PLACEMENT			SHOW MAKE & SPACING					
Centralizers - Middle first, top second & third. Then every third collar for a total of 20.								

COMPANY REPRESENTATIVE Alvin Nielsen

DATE 4/30/2008

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTAH STATE ML-16532

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL:

OIL WELL ☒ GAS WELL ☐ OTHER

2. NAME OF OPERATOR:

NEWFIELD PRODUCTION COMPANY

3. ADDRESS OF OPERATOR:

Route 3 Box 3630 CITY Myton STATE UT ZIP 84052

PHONE NUMBER

435.646.3721

8. WELL NAME and NUMBER:

STATE 2-16-9-16

9. API NUMBER:

4301333846

10. FIELD AND POOL, OR WILDCAT:

MONUMENT BUTTE

4. LOCATION OF WELL:

FOOTAGES AT SURFACE: 497 FNL 1982 FEL

COUNTY: DUCHESNE

OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: NWNE, 16, T9S, R16E

STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 06/23/2008	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Weekly Status Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The above subject well was completed on 05/28/08, attached is a daily completion status report.

NAME (PLEASE PRINT) Jentri Park

TITLE Production Clerk

SIGNATURE

DATE 06/23/2008

(This space for State use only)

RECEIVED

JUN 30 2008

DIV. OF OIL, GAS & MINING

Daily Activity Report**Format For Sundry****STATE 2-16-9-16****3/1/2008 To 7/30/2008****5/16/2008 Day: 1****Completion**

Rigless on 5/15/2008 - Install 5m frac head. NU 6" 5K Cameron BOP. RU H/O truck & pressure test casing, blind rams, frac head, csg & casing valves to 4500 psi. RU Perforators LLC WLT w/ mast & run CBL under pressure. WLTD @ 5735' & cement top @ 54'. Perforate stage #1, CP1 sds @ 5600-07' & 5546-56' w/ 3-1/8" Slick Guns (19 gram, .49"EH. 120°) w/ 4 spf for total of 68 shots. 138 BWTR. SWIFN.

5/22/2008 Day: 2**Completion**

Rigless on 5/21/2008 - Stage #1, CP1 sands. RU BJ Services. 0 psi on well. Frac CP1 sds w/ 15,030#'s of 20/40 sand in 274 bbls of Lightning 17 fluid. Broke @ 2435 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 1971 psi @ ave rate of 26.4 BPM. Pumped 504 gals of 15% HCL in flush for Stage #2. ISIP 1642 psi. Leave pressure on well. 412 BWTR Stage #2, LODC sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 11' perf gun. Set plug @ 5400'. Perforate LODC sds @ 5304-15' w/ 3-1/8" Slick Guns w/ 4 spf for total of 44 shots. RU BJ Services. 1281 psi on well. Frac LODC sds w/ 20,640#'s of 20/40 sand in 313 bbls of Lightning 17 fluid. Broke @ 3458 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2881 psi @ ave rate of 23 BPM. Pumped 504 gals of 15% HCL in flush for Stage #3. ISIP 2797 psi. Leave pressure on well. 725 BWTR Stage #3, C sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 10' perf gun. Set plug @ 4910'. Perforate C sds @ 4807-17' w/ 3-1/8" Slick Guns w/ 4 spf for total of 40 shots. RU BJ Services. 1975 psi on well. Frac C sds w/ 24,830#'s of 20/40 sand in 339 bbls of Lightning 17 fluid. Broke @ 2165 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2219 psi @ ave rate of 23 BPM. Pumped 504 gals of 15% HCL in flush for Stage #4. ISIP 2256 psi. Leave pressure on well. 1064 BWTR Stage #4, D2 & D3 sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug, 7' & 7' perf gun. Tagged sand @ 4723'. Unabe to set plug & perforate. POH w/ plug & guns. Flowback well for 3 hrs. Rec 180 BTF. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug, 7' & 7' perf gun. Set plug @ 4785'. Perforate D3 sds @ 4740-47', D2 @ 4718-25' w/ 3-1/8" Slick Guns w/ 4 spf for total of 56 shots. RU BJ Services. 100 psi on well. Started frac. Had trouble w/ chemical truck pumps. SIWFN w/ 884 BWTR.

5/23/2008 Day: 3**Completion**

Leed #731 on 5/22/2008 - Day 3. Stage #4, D2 & D3 sands. RU RU BJ Services. 50 psi on well. Frac D2 & D3 sds w/ 25,834#'s of 20/40 sand in 447 bbls of Lightning 17 fluid. Broke @ 2515 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2017 psi @ ave rate of 23.5 BPM. ISIP 2000 psi. Begin immediate flowback on 12/64 choke @ 1 BPM. Flowed for 2 hrs & died. Recovered 120 BTF. MIRU Leed 731. ND Cameron BOP & 5M WH. NU 3M WH & Schaffer BOP. Talley, PU & RIH w/ 4 3/4" Hurricane bit, bit sub & 60 jts of 2 7/8 J-55 tbg. SIWFN w/ 1211 BWTR.

5/24/2008 Day: 4**Completion**

Leed #731 on 5/23/2008 - Bleed pressure off well. Rec est 10 BTF. Con't PU & TIH W/ bit and tbg f/ 1920'. Tag fill @ 4670'. Tbg displaced 11 BW on TIH. RU power swivel. C/O sd & drill out composite bridge plugs as follows (using conventional circulation): sd @ 4670', plug @ 4785' in 15 minutes; sd @ 4855', plug @ 4910' in 10 minutes; sd @ 5382', plug @ 5400' in 15 minutes. Con't swivelling jts in hole. Tag fill @ 5676'. Drill plug remains & sd to PBTD @ 5794'. Circ hole clean W/ no fluid loss. RD swivel & pull EOT to 5698'. RU swab equipment. IFL @ sfc. Made 5 swb runs rec 70 BTF W/ light gas & tr oil & sd. FFL @ 1100'. SIFN W/ est 1120 BWTR.

5/28/2008 Day: 5

Completion

Leed #731 on 5/27/2008 - Bleed pressure off annulus--flowing oil. Flow back est 55 BTF (W/ est 25% oil cut & no sand). Circ hole W/ clean wtr. Lost est 30 BW & rec 20 BO. TIH W/ tbg. Tag PBTD @ 5794' (no new fill). LD excess tbg. TOH W/ tbg--LD bit. TIH W/ BHA & production tbg as follows: 2 7/8 NC, 2 jts tbg, SN, 1 jt tbg, new CDI 5 1/2" TA (45K) & 178 jts 2 7/8 8rd 6.5# J-55 tbg. ND BOP. Set TA @ 5558' W/ SN @ 5592' & EOT @ 5655'. Land tbg W/ 15,000# tension. NU wellhead. Flush tbg W/ 60 BW (returned same). PU & TIH W/ pump and rod string to 3100'. PU polished rod & SIFN W/ est 1109 BWTR.

5/29/2008 Day: 6

Completion

Leed #731 on 5/28/2008 - LD polished rod & con't PU "A & "B" grade rod string f/ 3100' (complete as follows): new CDI 2 1/2" X 1 1/2" X 15.5' RHAC pump, 6-1 1/2" weight rods (B), 20-3/4" scraped rods (B), 98-3/4" plain rods (B), 99-3/4" scraped rods (B), 1-8' X 3/4" pony rod (A) and 1 1/2" X 26' polished rod (A). Seat pump & RU pumping unit. Fill tbg W/ 2 BW. Pressure test tbg & pump to 200 psi. Stroke pump up W/ unit to 800 psi. Good pump action. RDMOSU. Est 1111 BWTR. Place well on production @ 3:00 PM 5/28/2008 W/ 56" SL @ 4.5 SPM. FINAL REPORT!!

Pertinent Files: Go to File List

(See other in-
structions on
reverse side)OMB NO. 1004-0137
Expires: February 28, 1995UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WORK

OIL WELL ☒ GAS WELL ☐ DRY ☐ Other _____

1b. TYPE OF WELL

NEW WELL ☒ WORK OVER ☐ DEEPEN ☐ PLUG BACK ☐ DIFF RESVR. ☐ Other _____

2. NAME OF OPERATOR

Newfield Exploration Company

3. ADDRESS AND TELEPHONE NO.

1401 17th St. Suite 1000 Denver, CO 80202

4. LOCATION OF WELL (Report locations clearly and in accordance with any State requirements.)*

At Surface 497' FNL & 1982' FEL (NW/NE) Sec. 16, T9S, R16E

At top prod. Interval reported below

At total depth

14. API NO. 013
43-03-33846 DATE ISSUED
02/25/089. WELL NO. 013
43-03-3384610. FIELD AND POOL OR WILDCAT
Monument Butte11. SEC., T., R., M., OR BLOCK AND SURVEY
OR AREA
Sec. 16, T9S, R16E12. COUNTY OR PARISH
Duchesne 13. STATE
UT

15. DATE SPUDDED 03/31/08 16. DATE T.D. REACHED 04/29/08 17. DATE COMPL. (Ready to prod.) 05/28/08 18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* 5809' GL 5821' KB 19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD & TVD 5810' 21. PLUG BACK T.D., MD & TVD 5794' 22. IF MULTIPLE COMPL., HOW MANY* 23. INTERVALS DRILLED BY -----> 24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)* Green River 4718'-5607' 25. WAS DIRECTIONAL SURVEY MADE No 26. TYPE ELECTRIC AND OTHER LOGS RUN Dual Induction Guard, SP, Compensated Density, Compensated Neutron, GR, Caliper, Cement Bond Log 27. WAS WELL CORED No

24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)*
Green River 4718'-5607'

26. TYPE ELECTRIC AND OTHER LOGS RUN

Dual Induction Guard, SP, Compensated Density, Compensated Neutron, GR, Caliper, Cement Bond Log

CASING RECORD (Report all strings set in well)					
CASING SIZE/GRADE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	TOP OF CEMENT, CEMENTING RECORD	AMOUNT PULLED
8-5/8" - J-55	24#	324'	12-1/4"	To surface with 160 sx Class "G" cmt	
5-1/2" - J-55	15.5#	5816'	7-7/8"	315 sx Premilite II and 415 sx 50/50 Poz	

LINER RECORD					TUBING RECORD		
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2-7/8"	EOT @ 5655'	TA @ 5558'

31. PERFORATION RECORD (Interval, size and number)			32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.		
INTERVAL	SIZE	SPF/NUMBER	DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED	
(CP1) 5600'-07', 5546'-5556'	.49"	4/68	5546'-5607'	Frac w/ 15,030# 20/40 sand in 274 bbls fluid	
(LODC) 5304'-5315'	.49"	4/44	5304'-5315'	Frac w/ 20,640# 20/40 sand in 313 bbls fluid	
(C) 4807'-4817'	.49"	4/40	4807'-4817'	Frac w/ 24,830# 20/40 sand in 339 bbls fluid	
(D3 &2) 4740'-4747', 4718'-4725'	.49"	4/56	4718'-4747'	Frac w/ 25,834# 20/40 san din 447 bbls fluid	

33.* PRODUCTION							
DATE FIRST PRODUCTION 05/28/08		PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump) 2-1/2" x 1-1/2" x 15.5' RHAC SM Plunger Pump				WELL STATUS (Producing or shut-in) PRODUCING	
DATE OF TEST 06-15-08	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD ----->	OIL--BBL. 53	GAS--MCF. 159	WATER--BBL. 7	GAS-OIL RATIO 3000
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE ----->	OIL--BBL.	GAS--MCF.	WATER--BBL.	OIL GRAVITY-API (CORR.)	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)
Sold & Used for Fuel JUL 14 2008 TEST WITNESSED BY

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records
SIGNED Jentri Park TITLE Production Tech DATE 7/9/2008

*(See Instructions and Spaces for Additional Data on Reverse Side)

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries);				38. GEOLOGIC MARKERS		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
			Well Name State 2-16-9-16	Garden Gulch Mkr	3637'	
				Garden Gulch 1	3849'	
				Garden Gulch 2	3958'	
				Point 3 Mkr	4211'	
				X Mkr	4476'	
				Y-Mkr	4510'	
				Douglas Creek Mkr	4630'	
				BiCarbonate Mkr	4868'	
				B Limestone Mkr	4981'	
				Castle Peak	5489'	
				Basal Carbonate	NP	
				Total Depth (LOGGERS	5828'	

STATE OF UTAH

DIVISION OF OIL, GAS, AND MINING

1. **SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.

Use "APPLICATION FOR PERMIT TO DRILL OR DEEPEN" form for such proposals.

OIL ☐ GAS ☐
WELL ☐ WELL ☒ OTHER ☐2. NAME OF OPERATOR
NEWFIELD PRODUCTION COMPANY3. ADDRESS AND TELEPHONE NUMBER
**Rt. 3 Box 3630, Myton Utah 84052
435-646-3721**4. LOCATION OF WELL

Footages **497 FNL 1982 FEL**

QQ, SEC, T, R, M: **NW/NE Section 16, T9S R16E**5. LEASE DESIGNATION AND SERIAL NO.
ML-165326. IF INDIAN, ALLOTTEE OR TRIBAL NAME
N/A7. UNIT AGREEMENT NAME
NA8. WELL NAME and NUMBER
STATE 2-16-9-169. API NUMBER
43-013-3384610. FIELD AND POOL, OR WILDCAT
MONUMENT BUTTECOUNTY **DUCHESNE**
STATE **UTAH**11. **CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA**

NOTICE OF INTENT:

(Submit in Duplicate)

<input type="checkbox"/> ABANDON	<input type="checkbox"/> NEW CONSTRUCTION
<input type="checkbox"/> REPAIR CASING	<input type="checkbox"/> PULL OR ALTER CASING
<input type="checkbox"/> CHANGE OF PLANS	<input type="checkbox"/> RECOMPLETE
<input type="checkbox"/> CONVERT TO INJECTION	<input type="checkbox"/> REPERFORATE
<input type="checkbox"/> FRACTURE TREAT OR ACIDIZE	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> MULTIPLE COMPLETION	<input type="checkbox"/> WATER SHUT OFF
<input type="checkbox"/> OTHER _____	

SUBSEQUENT REPORT OF:

(Submit Original Form Only)

<input type="checkbox"/> ABANDON*	<input type="checkbox"/> NEW CONSTRUCTION
<input type="checkbox"/> REPAIR CASING	<input type="checkbox"/> PULL OR ALTER CASING
<input checked="" type="checkbox"/> CHANGE OF PLANS	<input type="checkbox"/> RECOMPLETE
<input type="checkbox"/> CONVERT TO INJECTION	<input type="checkbox"/> REPERFORATE
<input type="checkbox"/> FRACTURE TREAT OR ACIDIZE	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> OTHER _____	

DATE WORK COMPLETED _____

Report results of Multiple Completion and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

*Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depth for all markers and zones pertinent to this work.)

As per a conversation with Helen Sadik MacDonald approval was given to go ahead and set the planned 290' of surface casing that is normally set on wells drilled within the Monument Butte field by Newfield Production. Subsequently 324' of surface casing was set on the above mentioned well.

13. NAME & SIGNATURE: Mandie Crozier TITLE Regulatory Specialist DATE 7/21/2008

(This space for State use only)

RECEIVED
JUL 25 2008
DIV. OF OIL, GAS & MINING



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

UNDERGROUND INJECTION CONTROL PERMIT


Cause No. UIC-415.1

Operator: Newfield Production Company
Well: State 2-16-9-16
Location: Section 16, Township 9 South, Range 16 East
County: Duchesne
API No.: 43-013-33846
Well Type: Enhanced Recovery (waterflood)

Stipulations of Permit Approval

1. Approval for conversion to Injection Well issued on February 12, 2014
2. Maximum Allowable Injection Pressure: 1,606 psig
3. Maximum Allowable Injection Rate: (restricted by pressure limitation)
4. Injection Interval: Green River Formation (3,957' – 5,794')
5. Any subsequent wells drilled within a ½ mile radius of this well shall have production casing cement brought up to or above the top of the unitized interval for the Greater Monument Butte Unit.

Approved by:


John Rogers
Associate Director

Date

4/3/2014

JR/MLR/js

cc: Bruce Suchomel, Environmental Protection Agency
Bureau of Land Management, Vernal
SITLA
Jill Loyle, Newfield Production Company, Denver
Newfield Production Company, Myton
Duchesne County
Well File

N:\O&G Reviewed Docs\ChronFile\UIC





GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

February 12, 2014

Newfield Production Company
1001 Seventeenth Street, Suite 2000
Denver, CO 80202

Subject: Greater Monument Butte Unit Well: State 2-16-9-16, Section 16, Township 9 South, Range 16 East, SLBM, Duchesne County, Utah, API Well # 43-013-33846


Ladies Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced well to a Class II injection well. Accordingly, the following stipulations shall apply for full compliance with this approval:

1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
2. Conformance with all conditions and requirements of the complete application submitted by Newfield Production Company.
3. A casing\tubing pressure test shall be conducted prior to commencing injection.
4. Pressure shall be monitored between the surface casing and the production casing on a regular basis. Any pressure changes observed shall be reported to the Division immediately.
5. The top of the injection interval shall be limited to a depth no higher than 3,957 feet in the State 2-16-9-16 well.

A final approval to commence injection will be issued upon satisfactory completion of the listed stipulations. If you have any questions regarding this approval or the necessary requirements, please contact Mark Reinbold at 801-538-5333 or Brad Hill at 801-538-5315.

Sincerely,



John Rogers
Associate Director

JR/MLR/js

cc: Bruce Suchomel, Environmental Protection Agency
Bureau of Land Management, Vernal
SITLA
Duchesne County
Newfield Production Company, Myton
Well File

N:\O&G Reviewed Docs\ChronFile\UIC





Legend

Oil & Gas Well Type

- APD-Approved Permit
- ⊙ DRL-Spudded (Drilling Commenced)
- ⌘ GIW-Gas Injection Well
- _{GS} GSW-Gas Storage Well
- × LA-Location Abandoned
- LOC-New Location Well
- ⊙ OPS-Drilling Operations Suspended
- ⊙ PA-Pugged & Abandoned
- ⊙ PGW-Producing Gas Well
- POW-Producing Oil Well *in ACR*
- ▲ RET-Returned APD
- ⊙ SGW-Shut-in Gas Well
- SOW-Shut-in Oil Well
- ⊙ TA-Temp Abandoned
- TW-Test Well
- ⌘ WDW-Water Disposal Well
- ⌘ WIW-Water Injection Well *in ACR*
- WSW-Water Supply Well

Cement Bond Tops State 2-16-9-16 API #43-013-33846 UIC-415.1

(updated 4/3/2014)

0 0.05 0.1 0.2 0.3 0.4 Miles



- 4585 Depth to top of suitable cement bond
- Well Bottom Hole Location
- Oil & Gas Wells Hole Directional Path
- Wells-CbltopsMaster 1-31-13
- DNR Oil Gas Wells Buffer
- County Boundaries
- PLSS Sections
- PLSS Townships

**DIVISION OF OIL, GAS AND MINING
UNDERGROUND INJECTION CONTROL PROGRAM
PERMIT
STATEMENT OF BASIS**

Applicant: Newfield Production Company **Well:** State 2-16-9-16

Location: 16/9S/16E **API:** 43-013-33846

Ownership Issues: The proposed well is located on State of Utah land. The well is located in the Greater Monument Butte Unit. Lands in the one-half mile radius of the well are administered by the BLM and the State of Utah. The Federal Government and the State of Utah are the mineral owners within the area of review (AOR). Newfield and other various individuals hold the leases in the unit. Newfield has provided a list of all surface, mineral and lease holders in the half-mile radius. Newfield is the operator of the Greater Monument Butte Unit. Newfield has submitted an affidavit stating that all owners and interest owners have been notified of their intent.

Well Integrity: The proposed well has surface casing set at 324 feet and has a cement top at the surface. A 5½ inch production casing is set at 5,816 feet. The cement bond log is somewhat problematic but appears to demonstrate adequate bond in this well up to about 2,680 feet or higher. A 2 7/8 inch tubing with a packer will be set at 4,668 feet. A mechanical integrity test will be run on the well prior to injection. At the time of this revision (4/3/2014), on the basis of surface locations, there are 5 producing wells, 6 injection wells, 1 shut-in well, and 2 P/A wells in the AOR. One of the producing wells is horizontally drilled with a surface location inside the AOR and a bottom hole location outside the AOR. In addition, there is one directionally drilled producing well with a surface location outside the AOR and a bottom hole location inside the AOR. Finally, there are 2 approved surface locations inside the AOR from which horizontal wells will be drilled to bottom hole locations outside the AOR and 1 surface location inside the AOR for a directional well to be drilled to a bottom hole location outside the AOR. The Castle Peak 32-16 (43-013-30650) well is located 0.3 mile south of the State 2-16 well. For this well, the original cement bond log (8/4/1982) demonstrates adequate bond up to about 4,512 feet. Newfield completed cement remediation in the Castle Peak 32-16 well on 6/24/2013, and a new CBL was run on 6/25/2013. The new CBL indicates variable but adequate cement between at least 3386 and 3634 feet. DOGM accepts 3386 feet as the top of adequate cement. Following this remediation, all of the existing wells in the AOR have evidence of adequate casing and cement for the proposed injection interval.

Ground Water Protection: As interpreted from the Utah Geological Survey's DOE Project-Uinta Basin Water Draft Map (Paul B. Anderson, December 2, 2011), the base of moderately saline water (3000-10,000 mg/l TDS) is at a depth of approximately 2600 feet. Injection shall be limited to the interval between 3,957 feet and 5,794 feet in the Green River Formation. Information submitted by Newfield indicates that the fracture gradient for the 2-16-9-16 well is

0.73 psi/ft., which was the lowest reported fracture gradient for the injection zone. The resulting minimum fracture pressure for the proposed injection interval is 1,606 psig. The requested maximum pressure is 1,606 psig. The anticipated average injection pressure is 1100 psig. Injection at this pressure should not initiate any new fractures or propagate existing fractures in the adjacent confining intervals. Any ground water present should be adequately protected.

Oil/Gas& Other Mineral Resources Protection: The Board of Oil, Gas & Mining approved the Greater Monument Butte Unit on December 1, 2009. Correlative rights issues were addressed at this time. Previous reviews in this area indicate that other mineral resources in the area have been protected or are not at issue.

Bonding: Bonded with the State of Utah

Actions Taken and Further Approvals Needed: A notice of agency action has been sent to the Salt Lake Tribune and the Uinta Basin Standard. A casing/tubing pressure test will be required prior to injection. It is recommended that approval of this application be granted.

Note: Applicable technical publications concerning water resources in the general vicinity of this project have been reviewed and taken into consideration during the permit review process.

Reviewer(s): Mark Reinbold Date: 2/11/2014 (revised 4/3/2014)

4770 S. 5600 W.
P.O. BOX 704005
WEST VALLEY CITY, UTAH 84170
FED.TAX I.D.# 87-0217663
801-204-6910

The Salt Lake Tribune

MEDIAONE

Deseret News

PROOF OF PUBLICATION

CUSTOMER'S COPY

CUSTOMER NAME AND ADDRESS	ACCOUNT NUMBER	DATE
DIV OF OIL-GAS & MINING, Rose Nolton 1594 W NORTH TEMP #1210 P.O. BOX 145801 SALT LAKE CITY, UT 84114	9001402352 BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH NOTICE OF AGENCY ACTION CAUSE NO. UIC-415	12/13/2013

ACCOUNT NAME	
DIV OF OIL-GAS & MINING,	
TELEPHONE	ADORDER
8015385340	0000927358
SCHEDULE	
Start 12/13/2013	End 12/13/2013
CUST. REF. NO.	
Newfield Cause UIC-415	
CAPTION	
BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT	
SIZE	
94 Lines	3.00
TIMES	
3	
MISC. CHARGES	
RECEIVED	
DEC 20 2013	

IN THE MATTER OF THE APPLICATION OF NEWFIELD PRODUCTION COMPANY FOR ADMINISTRATIVE APPROVAL OF CERTAIN WELLS LOCATED IN SECTIONS 16, 17, 18, 19, 20, 21, 23, AND 24, TOWNSHIP 9 SOUTH, RANGE 16 EAST, DUCHESNE COUNTY, UTAH, AS CLASS II INJECTION WELLS.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Newfield Production Company, 1001 17th Street, Suite 2000, Denver, Colorado 80202, telephone 303-893-0102, for administrative approval of the following wells located in Duchesne County, Utah, for conversion to Class II injection wells:

Greater Monument Butte Unit:

State 2-16-9-16 well located in NW/4 NE/4, Section 16, Township 9 South, Range 16 East
API 43-013-33846
State 13-16-9-16 well located in SW/4 SW/4, Section 16, Township 9 South, Range 16 East
API 43-013-33853
Castle Peak 32-16 well located in SW/4 NE/4, Section 16, Township 9 South, Range 16 East
API 43-013-30650
Federal 10-17-9-16 well located in NW/4 SE/4, Section 17, Township 9 South, Range 16 East
API 43-013-33033
Federal 12-17-9-16 well located in NW/4 SW/4, Section 17, Township 9 South, Range 16 East
API 43-013-33035
Federal 16-18-9-16 well located in SE/4 SE/4, Section 18, Township 9 South, Range 16 East
API 43-013-32922
Federal 2-19-9-16 well located in NW/4 NE/4, Section 19, Township 9 South, Range 16 East
API 43-013-33063
Federal 6-19-9-16 well located in SE/4 NW/4, Section 19, Township 9 South, Range 16 East
API 43-013-33100
Federal 12-19-9-16 well located in NW/4 SW/4, Section 19, Township 9 South, Range 16 East
API 43-013-33102
Federal 14-19-9-16 well located in SE/4 SW/4, Section 19, Township 9 South, Range 16 East
API 43-013-33161
Federal 16-19-9-16 well located in SE/4 SE/4, Section 19, Township 9 South, Range 16 East
API 43-013-33163
Federal 8-20-9-16 well located in SE/4 NE/4, Section 20, Township 9 South, Range 16 East
API 43-013-33107
Federal 3-21-9-16 well located in NE/4 NW/4, Section 21, Township 9 South, Range 16 East
API 43-013-33019
Federal 4-21-9-16 well located in NW/4 NW/4, Section 21, Township 9 South, Range 16 East
API 43-013-33069
Federal 8-21-9-16 well located in SE/4 NE/4, Section 21, Township 9 South, Range 16 East
API 43-013-33023
Federal 2-23-9-16 well located in NW/4 NE/4, Section 23, Township 9 South, Range 16 East
API 43-013-33003
Castle Peak Federal 6-23 well located in SE/4 NW/4, Section 23, Township 9 South, Range 16 East
API 43-013-30873
Federal 8-23-9-16 well located in SE/4 NE/4, Section 23, Township 9 South, Range 16 East
API 43-013-32961
Federal 14-24-9-16 well located in SE/4 SW/4, Section 24, Township 9 South, Range 16 East
API 43-013-33343

The proceeding will be conducted in accordance with Utah Admin. R649-10, Administrative Procedures.

Selected zones in the Green River Formation will be used for water injection. The maximum requested injection pressures and rates will be determined based on fracture gradient information submitted by Newfield Production Company.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for the proceeding is Brad Hill, Permitting Manager, at P.O. Box 145801, Salt Lake City, UT 84114-5801, phone number (801) 538-5340. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedural rules. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 11th day of December, 2013.

STATE OF UTAH
DIVISION OF OIL, GAS & MINING
/s/ Brad Hill
Permitting Manager

923768

UPAXLP

NOTARY PUBLICATION DATE AND REMAINS ON
UTAHLEGAL.COM INDEFINITELY. COMPLIES WITH UTAH DIGITAL SIGNATURE ACT UTAH CODE 46-2-101; 46-3-104.

VIRGINIA CRAFT
Notary Public State of Utah
Commission # 87160
My Commission Expires
January 12, 2014

NOTARY SIGNATURE

AS NEWSPAPER AGENCY COMPANY, LLC dba MEDIAONE OF UTAH LEGAL BOOKER, I C
BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RES
CAUSE NO. UIC-415 IN THE MATTER OF THE APPLICA FOR DIV OF OIL-GAS & MIN
COMPANY, LLC dba MEDIAONE OF UTAH, AGENT FOR THE SALT LAKE TRIBUNE AND D
ENGLISH LANGUAGE WITH GENERAL CIRCULATION IN UTAH, AND PUBLISHED IN SALT
NOTICE IS ALSO POSTED ON UTAHLEGALS.COM ON THE SAME DAY AS THE FIRST NEWSPAPER PUBLICATION DATE AND REMAINS ON
UTAHLEGALS.COM INDEFINITELY. COMPLIES WITH UTAH DIGITAL SIGNATURE ACT UTAH CODE 46-2-101; 46-3-104.

PUBLISHED ON Start 12/13/2013 End 12/13/2013

SIGNATURE

DATE 12/13/2013


THIS IS NOT A STATEMENT BUT A "PROOF OF PUBLICATION"
PLEASE PAY FROM BILLING STATEMENT

2210/REB/6131

AFFIDAVIT OF PUBLICATION

County of Duchesne,
STATE OF UTAH


I, Kevin Ashby on oath, say that I am the PUBLISHER of the Uintah Basin Standard, a weekly newspaper of general circulation, published at Roosevelt, State and County aforesaid, and that a certain notice, a true copy of which is hereto attached, was published in the full issue such newspaper for 1 consecutive issues, and that the first publication was on the 17 day of December, 20 13, and that the last publication of such notice was in the issue of such newspaper dated the 17 day of December, 20 13, and that said notice was published on Utahlegals.com on the same day as the first newspaper publication and the notice remained on Utahlegals.com until the end of the scheduled run.



Publisher

Subscribed and sworn to before me on this

23 day of December, 20 13

by Kevin Ashby.


Notary Public



NOTICE OF AGENCY ACTION CAUSE NO. UIC-415

BEFORE THE
DIVISION OF OIL,
GAS AND MINING,
DEPARTMENT OF
NATURAL RE-
SOURCE, STATE
OF UTAH.

IN THE MATTER
OF THE APPLICA-
TION OF NEW-
FIELD PRODUC-
TION COMPANY
FOR ADMINISTRA-
TIVE APPROVAL
OF CERTAIN
WELLS LOCATED
IN SECTIONS 16,
17, 18, 19, 20, 21, 23,
and 24, TOWNSHIP
9 SOUTH, RANGE
16 EAST, DUCH-
ESNE COUNTY,
UTAH, AS CLASS
II INJECTION
WELLS.

THE STATE OF
UTAH TO ALL PER-
SONS INTERESTED
IN THE ABOVE
ENTITLED MAT-
TER.

Notice is hereby
given that the Divi-
sion of Oil, Gas and
Mining (the "Divi-
sion") is commencing
an informal adjudi-
cative proceeding
to consider the ap-
plication of Newfield
Production Company,
1001 17th Street,

Continued on next page

Continued from
previous page

Suite 2000, Denver,
Colorado 80202, tele-
phone 303-893-0102,
for administrative ap-
proval of the following
wells located in Duch-
esne County, Utah, for
conversion to Class II
injection wells:

'Greater Monument
Butte Unit:

State 2-16-9-16 well
located in NW/4 NE/4,
Section 16, Township 9
South, Range 16 East
API 43-013-33846

State 13-16-9-16
well located in SW/4
SW/4, Section 16,
Township 9 South,
Range 16 East
API 43-013-33853

Castle Peak 32-16-
well located in SW/4
NE/4, Section 16,
Township 9 South,
Range 16 East
API 43-013-30650

Federal 40-17-9-
16 well located in
NW/4 SE/4, Section
17, Township 9 South,
Range 16 East
API 43-013-33033

Federal 12-17-9-
16 well located in
NW/4 SW/4, Section
17, Township 9 South,
Range 16 East
API 43-013-33035

Federal 16-18-9-
16 well located in
SE/4 SE/4, Section
18, Township 9 South,
Range 16 East
API 43-013-32922

Federal 2-19-9-16
well located in NW/4
NE/4, Section 19,
Township 9 South,
Range 16 East
API 43-013-33063

Federal 6-19-9-16
well located in SE/4
NW/4, Section 19,
Township 9 South,
Range 16 East
API 43-013-33100

Federal 12-19-9-
16 well located in
NW/4 SW/4, Section
19, Township 9 South,
Range 16 East
API 43-013-33102

Federal 14-19-9-
16 well located in
SE/4 SW/4, Section
19, Township 9 South,
Range 16 East

Federal 14-19-9-
16 well located in
SE/4 SW/4, Section
19, Township 9 South,
Range 16 East

Federal 14-19-9-
16 well located in
SE/4 SW/4, Section
19, Township 9 South,
Range 16 East

Any person desir-
ing to object to the
application or oth-
erwise intervene
in the proceeding, mu-
st file a written pro-
test or notice of inter-
vention with the Divi-
sion within fifteen da-
ys following publica-
tion of this notice. The
Division's Presiding C-
ler for the proceeding
is Brad Hill, Permitting
Manager, at P.O. Box
145801, Salt Lake City,
UT 84145-801, phone
number (801) 535-
5340. If such a protest
or notice of interven-
tion is received, a hear-
ing will be scheduled
in accordance with the
aforementioned admini-
strative procedural rules.
Protestants and/or inter-
veners should be prepared
to demonstrate at the
hearing how this matter
affects their interests.

Dated this 11th day
of December, 2013
STATE OF UTAH
DIVISION OF OIL
& GAS & MINING

/s/
Brad Hill
Permitting Manager
Published in the
Uintah Basin Standard
December 17, 2013

RECEIVED
DEC 24 2013

DIV. OF OIL GAS & MINING

Federal 14-19-9-
16 well located in
SE/4 SW/4, Section
19, Township 9 South,
Range 16 East

API 43-013-33161
Federal 16-19-9-

16 well located in
SE/4 SE/4, Section
19, Township 9 South,
Range 16 East

API 43-013-33163

Federal 8-20-9-16
well located in SE/4
NE/4, Section 20,
Township 9 South,
Range 16 East

API 43-013-33107

Federal 3-21-9-16
well located in NE/4
NW/4, Section 21,
Township 9 South,
Range 16 East

API 43-013-33019

Federal 4-21-9-16
well located in NW/4
NW/4, Section 21,
Township 9 South,
Range 16 East

API 43-013-33069

Federal 8-21-9-16
well located in SE/4
NE/4, Section 21,
Township 9 South,
Range 16 East

API 43-013-33023

Federal 2-23-9-16
well located in NW/4
NE/4, Section 23,
Township 9 South,
Range 16 East

API 43-013-33003

Castle Peak Federal
6-23 well located in
SE/4 NW/4, Section
23, Township 9 South,
Range 16 East

API 43-013-30873

Federal 8-23-9-16
well located in SE/4
NE/4, Section 23,
Township 9 South,
Range 16 East

API 43-013-32961

Federal 14-24-9-
16 well located in
SE/4 SW/4, Section
24, Township 9 South,
Range 16 East

API 43-013-33343

The proceeding will
be conducted in ac-
cordance with Utah
Admin. R649-10, Ad-
ministrative Proce-
dures.

Selected zones in the
Green River Formation
will be used for water
injection. The maxi-
mum requested injec-
tion pressures and rates
will be determined
based on fracture gra-
dient information sub-
mitted by Newfield
Production Company.

BEFORE THE DIVISION OF OIL, GAS AND MINING
DEPARTMENT OF NATURAL RESOURCES
STATE OF UTAH
NOTICE OF AGENCY ACTION
CAUSE NO. UIC-415

IN THE MATTER OF THE APPLICATION OF NEWFIELD PRODUCTION COMPANY FOR ADMINISTRATIVE APPROVAL OF CERTAIN WELLS LOCATED IN SECTIONS 16, 17, 18, 19, 20, 21, 23, and 24, TOWNSHIP 9 SOUTH, RANGE 16 EAST, DUCHESNE COUNTY, UTAH, AS CLASS II INJECTION WELLS.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Newfield Production Company, 1001 17th Street, Suite 2000, Denver, Colorado 80202, telephone 303-893-0102, for administrative approval of the following wells located in Duchesne County, Utah, for conversion to Class II injection wells:

Greater Monument Butte Unit:

State 2-16-9-16 well located in NW/4 NE/4, Section 16, Township 9 South, Range 16 East
API 43-013-33846
State 13-16-9-16 well located in SW/4 SW/4, Section 16, Township 9 South, Range 16 East
API 43-013-33853
Castle Peak 32-16 well located in SW/4 NE/4, Section 16, Township 9 South, Range 16 East
API 43-013-30650
Federal 10-17-9-16 well located in NW/4 SE/4, Section 17, Township 9 South, Range 16 East
API 43-013-33033
Federal 12-17-9-16 well located in NW/4 SW/4, Section 17, Township 9 South, Range 16 East
API 43-013-33035
Federal 16-18-9-16 well located in SE/4 SE/4, Section 18, Township 9 South, Range 16 East
API 43-013-32922
Federal 2-19-9-16 well located in NW/4 NE/4, Section 19, Township 9 South, Range 16 East
API 43-013-33063
Federal 6-19-9-16 well located in SE/4 NW/4, Section 19, Township 9 South, Range 16 East
API 43-013-33100
Federal 12-19-9-16 well located in NW/4 SW/4, Section 19, Township 9 South, Range 16 East
API 43-013-33102
Federal 14-19-9-16 well located in SE/4 SW/4, Section 19, Township 9 South, Range 16 East
API 43-013-33161
Federal 16-19-9-16 well located in SE/4 SE/4, Section 19, Township 9 South, Range 16 East
API 43-013-33163
Federal 8-20-9-16 well located in SE/4 NE/4, Section 20, Township 9 South, Range 16 East
API 43-013-33107
Federal 3-21-9-16 well located in NE/4 NW/4, Section 21, Township 9 South, Range 16 East
API 43-013-33019
Federal 4-21-9-16 well located in NW/4 NW/4, Section 21, Township 9 South, Range 16 East
API 43-013-33069
Federal 8-21-9-16 well located in SE/4 NE/4, Section 21, Township 9 South, Range 16 East
API 43-013-33023
Federal 2-23-9-16 well located in NW/4 NE/4, Section 23, Township 9 South, Range 16 East
API 43-013-33003

Castle Peak Federal 6-23 well located in SE/4 NW/4, Section 23, Township 9 South, Range 16 East
API 43-013-30873

Federal 8-23-9-16 well located in SE/4 NE/4, Section 23, Township 9 South, Range 16 East
API 43-013-32961

Federal 14-24-9-16 well located in SE/4 SW/4, Section 24, Township 9 South, Range 16 East
API 43-013-33343


The proceeding will be conducted in accordance with Utah Admin. R649-10, Administrative Procedures.

Selected zones in the Green River Formation will be used for water injection. The maximum requested injection pressures and rates will be determined based on fracture gradient information submitted by Newfield Production Company.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for the proceeding is Brad Hill, Permitting Manager, at P.O. Box 145801, Salt Lake City, UT 84114-5801, phone number (801) 538-5340. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedural rules. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 11th day of December, 2013.

STATE OF UTAH
DIVISION OF OIL, GAS & MINING



Brad Hill
Permitting Manager

Newfield Production Company

**STATE 2-16-9-16, STATE 13-16-9-16, CASTLE PEAK 32-16,
FEDERAL 10-17-9-16, FEDERAL 12-17-9-16, FEDERAL 16-18-9-16,
FEDERAL 2-19-9-16, FEDERAL 6-19-9-16, FEDERAL 12-19-9-16,
FEDERAL 14-19-9-16, FEDERAL 16-19-9-16, FEDERAL 8-20-9-16,
FEDERAL 3-21-9-16, FEDERAL 4-21-9-16, FEDERAL 8-21-9-16,
FEDERAL 2-23-9-16, CASTLE PEAK FEDERAL 6-23,
FEDERAL 8-23-9-16, FEDERAL 14-24-9-16**

Cause No. UIC-415

Publication Notices were sent to the following:

Newfield Production Company
1001 17th Street, Suite 2000
Denver, CO 80202

SITLA
675 E 500 S Ste 500
Salt Lake City, UT 84102-2818

Uintah Basin Standard
268 South 200 East
Roosevelt, UT 84066
via e-mail ubs@ubstandard.com


Duchesne County Planning
P O Box 317
Duchesne, UT 84021-0317

Salt Lake Tribune
P O Box 45838
Salt Lake City, UT 84145
via e-mail naclegal@mediaoneutah.com

Bruce Suchomel
US EPA Region 8
MS 8P-W-GW
1595 Wynkoop Street
Denver, CO 80202-1129

Vernal Office
Bureau of Land Management
170 South 500 East
Vernal, UT 84078

Newfield Production Company
Rt 3 Box 3630
Myton, UT 84052





GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

December 12, 2013

Via e-mail: legals@ubstandard.com

Uintah Basin Standard
268 South 200 East
Roosevelt, UT 84066

Subject: Notice of Agency Action – Newfield Production Company Cause No. UIC-415

To Whom It May Concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please notify me via e-mail of the date it will be published. My e-mail address is: jsweet@utah.gov.

Please send proof of publication and billing to:

Division of Oil, Gas and Mining
PO Box 145801
Salt Lake City, UT 84114-5801

Sincerely,

Jean Sweet
Executive Secretary

Enclosure



Jean Sweet <jsweet@utah.gov>

Re: Notice of Agency Action – Newfield Production Company Cause No. UIC-415

1 message

UB Standard Legals <ubslegals@ubmedia.biz>

Thu, Dec 12, 2013 at 1:22 PM

To: Jean Sweet <jsweet@utah.gov>

On 12/12/2013 11:59 AM, Jean Sweet wrote:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please notify me via e-mail of the date it will be published. My e-mail address is: jsweet@utah.gov.

Please send proof of publication and billing to:

Division of Oil, Gas and Mining

PO Box 145801

Salt Lake City, UT 84114-5801

Sincerely,

Jean

—

Jean Sweet

Executive Secretary

Utah Division of Oil, Gas and Mining

801-538-5329

This will publish Dec. 17. Thank you. Merry Christmas.
Cindy



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

December 12, 2013

VIA E-MAIL naclegal@mediaoneutah.com

Salt Lake Tribune
P. O. Box 45838
Salt Lake City, UT 84145

Subject: Notice of Agency Action – Newfield Production Company Cause No. UIC-415

To Whom It May Concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please notify me via e-mail of the date it will be published. My e-mail address is: jsweet@utah.gov.

Please send proof of publication and billing for **account #9001402352** to:

Division of Oil, Gas and Mining
PO Box 145801
Salt Lake City, UT 84114-5801

Sincerely,

Jean Sweet
Executive Secretary

Enclosure



Jean Sweet <jsweet@utah.gov>

Proof for Notice

1 message

Stowe, Ken <naclegal@mediaoneutah.com>

Thu, Dec 12, 2013 at 12:34 PM

Reply-To: "Stowe, Ken" <naclegal@mediaoneutah.com>

To: jsweet@utah.gov

AD# 927358

Run SL Trib & Des News 12/13

Cost \$478.76

Thank You



OrderConf.pdf

185K

Order Confirmation for Ad #0000927358-01

Client	DIV OF OIL-GAS & MINING	Payor Customer	DIV OF OIL-GAS & MINING
Client Phone	801-538-5340	Payor Phone	801-538-5340
Account#	9001402352	Payor Account	9001402352
Address	1594 W NORTH TEMP #1210,P.O. BOX 145801 SALT LAKE CITY, UT 84114 USA	Payor Address	1594 W NORTH TEMP #1210,P.O. BOX SALT LAKE CITY, UT 84114
Fax	801-359-3940	Ordered By	Acct. Exec
EEmail	juliecarter@utah.gov	Jean	kstowe

Total Amount **\$478.76**

Payment Amt **\$0.00**

	<u>Tear Sheets</u>	<u>Proofs</u>	<u>Affidavits</u>
Amount Due	\$478.76	0	0
			1

Payment Method **PO Number** Newfield Cause UIC-4

Confirmation Notes:

Text: Jean

Ad Type	Ad Size	Color
Legal Liner	3.0 X 94 Li	<NONE>

<u>Product</u>	<u>Placement</u>	<u>Position</u>
Salt Lake Tribune::	Legal Liner Notice - 0998	998-Other Legal Notices
Scheduled Date(s):	12/13/2013	

<u>Product</u>	<u>Placement</u>	<u>Position</u>
Deseret News::	Legal Liner Notice - 0998	998-Other Legal Notices
Scheduled Date(s):	12/13/2013	

<u>Product</u>	<u>Placement</u>	<u>Position</u>
utahlegals.com::	utahlegals.com	utahlegals.com
Scheduled Date(s):	12/13/2013	

Order Confirmation for Ad #0000927358-01

Ad Content Proof Actual Size

NEWFIELD



Newfield Exploration Company

1001 17th Street | Suite 2000

Denver, Colorado 80202

PH 303-893-0102 | FAX 303-893-0103

November 27, 2013

Mr. Mark Reinbold
State of Utah
Division of Oil, Gas and Mining
1594 W North Temple
Salt Lake City, Utah 84114-5801

RECEIVED
DEC 03 2013
DIV. OF OIL, GAS & MINING

RE: Permit Application for Water Injection Well
State #2-16-9-16
Monument Butte Field, Lease #ML-16532
Section 16-Township 9S-Range 16E
Duchesne County, Utah

Dear Mr. Reinbold:

Newfield Production Company herein requests approval to convert the State #2-16-9-16 from a producing oil well to a water injection well in the Monument Butte (Green River) Field.

I hope you find this application complete; however, if you have any questions or require additional information, please contact me at (303) 893-0102.

Sincerely,



Jill L Loyle
Regulatory Associate


NEWFIELD PRODUCTION COMPANY
APPLICATION FOR APPROVAL OF CLASS II INJECTION WELL
STATE #2-16-9-16
MONUMENT BUTTE FIELD (GREEN RIVER) FIELD
LEASE #ML-16532
NOVEMBER 26, 2013

TABLE OF CONTENTS

LETTER OF INTENT	
COVER PAGE	
TABLE OF CONTENTS	
UIC FORM 1 – APPLICATION FOR INJECTION WELL	
WELLBORE DIAGRAM OF PROPOSED INJECTION	
WORK PROCEDURE FOR INJECTION CONVERSION	
COMPLETED RULE R615-5-1 QUESTIONNAIRE	
COMPLETED RULE R615-5-2 QUESTIONNAIRE	
ATTACHMENT A	ONE-HALF MILE RADIUS MAP
ATTACHMENT A-1	WELL LOCATION PLAT
ATTACHMENT B	LIST OF SURFACE OWNERS WITHIN ONE-HALF MILE RADIUS
ATTACHMENT C	CERTIFICATION FOR SURFACE OWNER NOTIFICATION
ATTACHMENT E	WELLBORE DIAGRAM – STATE #2-16-9-16
ATTACHMENT E-1	WELLBORE DIAGRAM – STATE #3-16-9-16
ATTACHMENT E-2	WELLBORE DIAGRAM – STATE #4-16-9-16
ATTACHMENT E-3	WELLBORE DIAGRAM – STATE #6-16-9-16
ATTACHMENT E-4	WELLBORE DIAGRAM – FEDERAL #14-9-9-16
ATTACHMENT E-5	WELLBORE DIAGRAM – FEDERAL #15-9-9-16
ATTACHMENT E-6	WELLBORE DIAGRAM – CASTLE PEAK #32-16-9-16
ATTACHMENT E-7	WELLBORE DIAGRAM – STATE #1-16-9-16
ATTACHMENT E-8	WELLBORE DIAGRAM – GMBU #T-9-9-16
ATTACHMENT E-9	WELLBORE DIAGRAM – SOUTH WELLS DRAW #16-9-9-16
ATTACHMENT E-10	WELLBORE DIAGRAM – SOUTH WELLS DRAW #13-10-9-16
ATTACHMENT F	WATER ANALYSIS
ATTACHMENT G	FRACTURE GRADIENT CALCULATIONS
ATTACHMENT G-1	FRACTURE REPORTS DATED – 5/16/2008 – 5/29/2008
ATTACHMENT H	WORK PROCEDURE FOR PROPOSED PLUG AND ABANDON
ATTACHMENT H-1	WELLBORE DIAGRAM OF PROPOSED PLUGGED WELL

APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR	Newfield Production Company
ADDRESS	1001 17th Street, Suite 2000
	Denver, Colorado 80202

Well Name and number:		State #2-16-9-16	
Field or Unit name: Monument Butte (Green River)		Lease No. ML-16532	
Well Location: QQ NWNE		section 16	township 9S range 16E county Duchesne
Is this application for expansion of an existing project? Yes [X] No []			
Will the proposed well be used for:		Enhanced Recovery? Yes [X] No []	
		Disposal? Yes [] No [X]	
		Storage? Yes [] No [X]	
Is this application for a new well to be drilled? Yes [] No [X]			
If this application is for an existing well,			
has a casing test been performed on the well? Yes [] No [X]			
Date of test:			
API number: 43-013-33846			
Proposed injection interval: from 3957 to 5794			
Proposed maximum injection: rate 500 bpd pressure 1606 psig			
Proposed injection zone contains [x] oil, [] gas, and/or [] fresh water within 1/2 mile of the well.			
IMPORTANT: Additional information as required by R615-5-2 should accompany this form.			
List of Attachments: Attachments "A" through "H-1"			
I certify that this report is true and complete to the best of my knowledge.			
Name: Jill L. Loyle		Signature: 	
Title: Regulatory Associate		Date: 27 Nov 2013	
Phone No. 303-383-4135			
(State use only)			
Application approved by		Title	
Approval Date			
Comments:			

State 2-16-9-16

Spud Date: 3/31/08

Put on Production: 5/28/08
GL: 5809' KB: 5821'

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts (314.36')

DEPTH LANDED: 324.36'

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sx Class "G", circ. 3 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 141 jts (5817.67')

HOLE SIZE: 7-7/8"

DEPTH LANDED: 5815.67'

CEMENT DATA: 315 sxs Prem. Lite II & 415 sxs 50/50 Poz

CEMENT TOP AT: 54' per CBL 5/15/08

TUBING (GI 4/5/11)

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#

NO. OF JOINTS: 178 jts (5548.8')

TUBING ANCHOR: 5560.8'

NO. OF JOINTS: 1 jt (31.5')

SEATING NIPPLE: 2-7/8" (1.10')


SN LANDED AT: 5595.1' KB

NO. OF JOINTS: 2 jts (62.1')

NOTCHED COLLAR: 2-7/8" (0.5')

TOTAL STRING LENGTH: EOT @ 5659' KB

Proposed Injection Wellbore Diagram



FRAC JOB

05-21-08 5546-5556' **Frac CPI sds as follows:**
15,030# 20/40 sand in 274 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1971 psi @ ave rate of 26.4 BPM. ISIP 1642 psi. Actual Flush: 5040 gals.

05-21-08 5304-5315' **Frac LODC sds as follows:**
20,640# 20/40 sand in 313 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2881 psi @ ave rate of 23 BPM. ISIP 2797 psi. Actual Flush: 4801 gals.

05-21-08 4807-4817' **Frac C sds as follows:**
24,830# 20/40 sand in 339 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2219 psi @ ave rate of 23 BPM. ISIP 2256 psi. Actual Flush: 4330 gals.

05-22-08 4718-4725' **Frac D2 & D3 sds as follows:**
25,834# 20/40 sand in 447 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2017 psi @ ave rate of 23.5 BPM. ISIP 2000 psi. Actual flush: 4670 gals.

2/18/09

Tubing Leak. Updated r & t details.

4/7/11

Tubing leak. Updated Rod & tubing details.

PERFORATION RECORD

4718-4725'	4 JSPF	28 holes
4740-4747'	4 JSPF	28 holes
4807-4817'	4 JSPF	40 holes
5304-5315'	4 JSPF	44 holes
5546-5556'	4 JSPF	40 holes
5600-5607'	4 JSPF	28 holes

NEWFIELD

State 2-16-9-16
497' FNL & 1982' FEL
NW/NE Section 16-T9S-R16E
Duchesne Co, Utah
API #43-013-33846; Lease #ML-16532

JL 11/25/2013

WORK PROCEDURE FOR INJECTION CONVERSION

1. Rig up hot oil truck to casing. Pump water. Unseat pump. Flush rods. Trip out of hole with rods and pump.
2. Trip out of hole with tubing, breaking and doping every connection. Trip in hole with packer and tubing. Rig up water truck to casing. Pump packer fluid. Set packer.
3. Test casing and packer.
4. Rig down and move out.

**REQUIREMENTS FOR INJECTION OF FLUIDS INTO RESERVOIRS
RULE R615-5-1**

- 1. Operations to increase ultimate recovery, such as cycling of gas, the maintenance of pressure, the introduction of gas, water or other substances into a reservoir for the purpose of secondary or other enhanced recovery or for storage and the injection of water into any formation for the purpose of water disposal shall be permitted only by order of the Board after notice and hearing.**
- 2. A request for agency action for authority for the injection of gas, liquified petroleum gas, air, water or any other medium into any formation for any reason, including but not necessarily limited to the establishment of or the expansion of waterflood projects, enhanced recovery projects, and pressure maintenance projects shall contain:**

2.1 The name and address of the operator of the project.

Newfield Production Company
1001 17th Street, Suite 2000
Denver, Colorado 80202

2.2 A plat showing the area involved and identifying all wells, including all proposed injection wells, in the project area and within one-half mile of the project area.

See Attachment A.

2.3 A full description of the particular operation for approval is requested.

Approval is requested to convert the State #2-16-9-16 from a producing oil well to a water injection well in Monument Butte (Green River) Field.

2.4 A description of the pools from which the identified wells are producing or have produced.

The proposed injection well will inject into the Green River Formation.

2.5 The names, description and depth of the pool or pools to be affected.

The injection zone is in the Green River Formation. For the State #2-16-9-16 well, the proposed injection zone is from Garden Gulch to Castle Peak (3957' - 5794'). The confining strata directly above and below the injection zones are the Garden Gulch and the top of the Wasatch Formation or TD, which ever is shallower. The Garden Gulch Marker top is at 3636' and the TD is at 5810'.

2.6 A copy of a log of a representative well completed in the pool.

The referenced log for the State #2-16-9-16 is on file with the Utah Division of Oil, Gas and Mining.

- 2.7 A statement as to the type of fluid to be used for injection, its source and the estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be culinary water commingled with produced water. The average estimated injection of fluids will be at a rate of 300 BPD, and the estimated maximum injection will be at a rate of 500 BPD.

- 2.8 A list of all operators and surface owners within one-half mile radius of the proposed project.**

See Attachment B.

- 2.9 An affidavit certifying that said operators or owners and surface owners within a one-half mile radius have been provided a copy of the petition for injection.**

See Attachment C.

- 2.10 Any additional information the Board may determine is necessary to adequately review the petition.**

Newfield Production Company will supply any additional information requested by the Utah Division of Oil, Gas and Mining.

- 4.0 Establish recovery projects may be expanded and additional wells placed on injection only upon authority from the Board after notice and hearing or by administrative approval.**

This proposed injection well is on a State lease (Lease #ML-16532) in the Monument Butte Federal (Green River) Field, and this request is for administrative approval.

**REQUIREMENTS FOR CLASS II INJECTION WELLS INCLUDING WATER DISPOSAL,
STORAGE AND ENHANCED RECOVERY WELLS
SECTION V – RULE R615-5-2**

- 1. Injection well shall be completed, equipped, operated, and maintained in a manner that will prevent pollution and damage to any USDW, or other resources and will confine injected fluids to the interval approved.**
- 2. The application for an injection well shall include a properly completed Form DOGM-UIC-1 and the following:**

- 2.1 A plat showing the location of the injection well, all abandoned or active wells within a one-half mile radius of the proposed wells, and the surface owner and the operator of any lands or producing leases, respectively, within a one-half mile radius of the proposed injection well.**

See Attachments A and B.

- 2.2 Copies of electrical or radioactive logs, including gamma ray logs, for the proposed well run prior to the installation of casing and indicating resistivity, spontaneous potential, caliper and porosity.**

All logs are on file with the Utah Division of Oil, Gas and Mining.

- 2.3 A copy of a cement bond or comparable log run for the proposed injection well after casing was set and cemented.**

A copy of the cement bond log is on file with the Utah Division of Oil, Gas and Mining.

- 2.4 Copies of logs already on file with the Division should be referenced, but need not be refiled.**

All copies of logs are on file with the Utah Division of Oil, Gas and Mining.

- 2.5 A description of the casing or proposed casing program of the injection well and of the proposed method for testing the casing before use of the well.**

The casing program is 8-5/8", 24# surface casing run to 324' KB, and 5-1/2", 15.5# casing run from surface to 5816' KB. A casing integrity test will be conducted at the time of conversion. See Attachment E.

- 2.6 A statement as to the type of fluid to be used for injection, its source and estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be culinary water commingled with produced water. The estimated average rate of injection will be 300 BPD, and the estimated maximum rate of injection will be 500 BPD.

- 2.7 Standard laboratory analysis of the fluid to be injected, the fluid in the formation into which the fluid is being injected, and the compatibility of the fluids.**

See Attachment F.

2.8 The proposed average and maximum injection pressures.

The proposed average injection pressure will be approximately 1100 psig and the maximum injection pressure will not exceed 1606 psig.

2.9 Evidence and data to support a finding that the proposed injection well will not initiate fractures through the overlying strata or a confining interval that could enable the injected fluid or formation fluid to enter the fresh water strata.

The minimum fracture gradient for the State #2-16-9-16, for existing perforations (4718' - 5556') calculates at 0.73 psig/ft. The maximum injection pressures will be limited so as not to exceed this gradient. A step rate test will be performed periodically to ensure we are below parting pressure. The proposed maximum injection pressure is 1606 psig. We may add additional perforations between 3636' and 5810'. See Attachments G and G-1.

2.10 Appropriate geological data on the injection interval and confining beds, including the geologic name, lithologic description, thickness, depth, and lateral extent.

In the State #2-16-9-16, the proposed injection zone (3957' - 5794') is in the Garden Gulch to the Castle Peak of the Green River Formation. The reservoir is a very fine-grained sandstone with minor imbedded shale streaks. The estimated porosity is 13%. The members are composed of porous and permeable lenticular calcareous sandstone and low porosity carbonates and calcareous shale. The porous and lenticular sandstone varies in thickness from 0-31' and is confined to the Monument Butte Federal Field. Outside the Monument Butte Federal Field, the sandstone is composed of tight, very fine, silty, calcareous sandstone, less than 3' thick. The stratum confining the injection zone is composed of tight, moderately calcareous, sandy lacustrine shale. All of the confining strata are impermeable, and will effectively seal off the oil, gas, and water of the injection zone from any strata directly above or below it.

2.11 A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter the improper intervals.

See Attachments E through E-10.


Additionally, the injection system will be equipped with high and low pressure shut down devices that will automatically shut in injection waters if a system blockage or leakage occurs. One way check valves will also ensure proper flow management. Relief valves will also be utilized for high-pressure relief.

2.12 An affidavit certifying that a copy of the application has been provided to all operators or owners, and surface owners within a one-half mile radius of the proposed injection well.

See Attachment C.

2.13 Any other information that the Board or Division may determine is necessary to adequately review the application.

Newfield Production Company will supply any requested information to the Board or Division.





T9S, R16E, S.L.B.&M.


N89°50'W - 80.24 (G.L.O.)

NEWFIELD PRODUCTION COMPANY

WELL LOCATION, 9 MILE 2-16-9-16,
LOCATED AS SHOWN IN THE NW 1/4 NE
1/4 OF SECTION 16, T9S, R16E,
S.L.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST OF
MY KNOWLEDGE AND BELIEF. No. 189377



◆ = SECTION CORNERS LOCATED

BASIS OF ELEV;
U.S.G.S. 7-1/2 min QUAD (MYTON SE)

9 MILE 2-16-9-16
(Surface Location) NAD 83
LATITUDE = 40° 02' 12.17"
LONGITUDE = 110° 07' 18.94"

TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 10-11-07	SURVEYED BY: C.M.
DATE DRAWN: 11-01-07	DRAWN BY: F.T.M.
REVISED:	SCALE: 1" = 1000'

EXHIBIT B

#	Legal Description	Lessor & Expiration	Lessee & Operating Rights	Surface Owner
1	T9S-616E SLM Section 16: All	State of Utah ML 16532 HBP	Newfield RMI LLC QEP Energy Company El Paso E&P Company LP American Petroleum Corp Brave River Production Trans Republic Resources Inc	State of Utah
2	T9S-R16E SLM Section 9: N2SE, SESE	USA UTU-40894 HBP	Newfield Production Company Newfield RMI LLC	USA
3	T9S-R16E SLM Section 8: SWNE, SE Section 9: SWSW Section 17: NE Section 18: E2SW, SE, LOTS 3, 4 Section 19: NE, E2NW, LOTS 1, 2 Section 21: N2 Section 22: W2NE, SENE, NW	USA UTU-64379 HBP	Newfield Production Company Newfield RMI LLC Yates Petroleum Corp	USA
4	T9S-R16E SLM Section 10: S2N2, N2S2, S2SW	USA UTU-72107 HBP	Newfield Production Company Newfield RMI LLC	USA
5	T9S-R16E SLM Section 9: E2SW, SWSE	USA UTU-79831 HBP	Newfield Production Company Newfield RMI LLC	USA
6	T9S-R16E SLM Section 15: W2W2	USA UTU-79834 HBP	Newfield Production Company Newfield RMI LLC	USA


ATTACHMENT C

CERTIFICATION FOR SURFACE OWNER NOTIFICATION

RE: Application for Approval of Class II Injection Well
State #2-16-9-16

I hereby certify that a copy of the injection application has been provided to all surface owners within a one-half mile radius of the proposed injection well.

Signed:


Newfield Production Company
Jill L. Loyle
Regulatory Associate

Sworn to and subscribed before me this 27th day of November, 2013.

Notary Public in and for the State of Colorado: Michelle S. Gonzales

My Commission Expires: 11/08/2014

MICHELLE S GONZALES
Notary Public
State of Colorado

State 2-16-9-16

Spud Date: 3/31/08

Put on Production: 5/28/08

GL: 5809' KB: 5821'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts (314.36')

DEPTH LANDED: 324.36'

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sx Class "G", circ. 3 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 141 jts (5817.67')

HOLE SIZE: 7-7/8"

DEPTH LANDED: 5815.67'

CEMENT DATA: 315 sxs Prem, Lite II & 415 sxs 50/50 Poz

CEMENT TOP AT: 54' per CBL 5/15/08

TUBING (GI 4/5/11)

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#

NO. OF JOINTS: 178 jts (5548.8')

TUBING ANCHOR: 5560.8'

NO. OF JOINTS: 1 jt (31.5')

SEATING NIPPLE: 2-7/8" (1.10')

SN LANDED AT: 5595.1' KB

NO. OF JOINTS: 2 jts (62.1')

NOTCHED COLLAR: 2-7/8" (0.5')

TOTAL STRING LENGTH: EOT @ 5659' KB

SUCKER RODS (GI 4/5/11)

POLISHED ROD: 1-1/2" x 26' polished rod

SUCKER RODS: 8', 4', 4' 7/8" pony rods, 97 x 3/4" guided rods, 79 x 3/4" guided rods, 40 x 3/4" guided rods, 6 x 1-1/2" weight rods, 6(4') x 1" stabilizer rods.

PUMP SIZE: 2-1/2" x 1-1/4" x 16 RHAC

STROKE LENGTH: 63"

PUMP SPEED, SPM: 4

PUMPING UNIT: LUFKIN C-228-212-86

FRAC JOB

05-21-08 5546-5556' **Frac CP1 sds as follows:**
15,030# 20/40 sand in 274 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1971 psi @ ave rate of 26.4 BPM. ISIP 1642 psi. Actual Flush: 5040 gals.


05-21-08 5304-5315' **Frac LODC sds as follows:**
20,640# 20/40 sand in 313 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2881 psi @ ave rate of 23 BPM. ISIP 2797 psi. Actual Flush: 4801 gals.

05-21-08 4807-4817' **Frac C sds as follows:**
24,830# 20/40 sand in 339 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2219 psi @ ave rate of 23 BPM. ISIP 2256 psi. Actual Flush: 4330 gals.

05-22-08 4718-4725' **Frac D2 & D3 sds as follows:**
25,834# 20/40 sand in 447 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2017 psi @ ave rate of 23.5 BPM. ISIP 2000 psi. Actual flush: 4670 gals.

2/18/09 Tubing Leak. Updated r & t details.

4/7/11 Tubing leak. Updated Rod & tubing details.

PERFORATION RECORD

4718-4725'	4 JSPF	28 holes
4740-4747'	4 JSPF	28 holes
4807-4817'	4 JSPF	40 holes
5304-5315'	4 JSPF	44 holes
5546-5556'	4 JSPF	40 holes
5600-5607'	4 JSPF	28 holes



State 2-16-9-16
497' FNL & 1982' FEL
NW/NE Section 16-T9S-R16E
Duchesne Co, Utah
API #43-013-33846; Lease #ML-16532

TD @ 5810'

Spud Date: 02-28-08
 Put on Production: 05-13-08
 GL: 5841' KB: 5853'

State 3-16-9-16

Injection Wellbore
DiagramSURFACE CASING


CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 10 jts
 DEPTH LANDED: 443'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: To surface with 209 sx Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 147 jts
 HOLE SIZE: 7-7/8"
 DEPTH LANDED: 5855.97'
 CEMENT DATA: 300 sk Prem. Lite II mixed & 400 sxs 50/50 POZ.
 CEMENT TOP AT: 278'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 148 jts (4526.9')
 SEATING NIPPLE: 2-7/8" (1.10')
 SN LANDED AT: 4538.9' KB
 ON/OFF TOOL AT: 4540.0'
 ARROW #1 PACKER CE AT: 4545'
 XO 2-3/8 x 2-7/8 J-55 AT: 4548.8'
 TBG PUP 2-3/8 J-55 AT: 4549.3'
 X/N NIPPLE AT: 4553.4'
 TOTAL STRING LENGTH: EOT @ 4555'

FRAC JOB

04-22-08	5571-5592'	Frac CP1 sds as follows: Frac w/144,428# 20/40 sand in 1022 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1764 psi w/ ave rate of 25.2 BPM. ISIP 2006 psi. Actual Flush: 5065 gals.
04-22-08	5203-5211'	Frac LODC sds as follows: Frac w/24,817# 20/40 sand in 356 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2477 psi w/ ave rate of 23.3 BPM. ISIP 2543. Actual Flush: 4696 gals.
04-22-08	5094-5109'	Frac A1 sds as follows: Frac w/38,375# 20/40 sand in 420 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2034 psi w/ ave rate of 23.3 BPM. ISIP 2543 psi. Actual Flush: 4586 gals.
04-22-08	4944-4954'	Frac B2 sds as follows: Frac w/30,349# 20/40 sand in 383 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1804 psi w/ ave rate of 23.3 BPM. ISIP 1842 psi. Actual Flush: 4439 gals.
04-22-08	4824-4839'	Frac C sds as follows: Frac w/48,027# 20/40 sand in 446 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2057 psi w/ ave rate of 23.3 BPM. ISIP 2063 psi. Actual Flush: 4318 gals.
04-22-08	4710-4724'	Frac D2 sds as follows: Frac w/37,944# 20/40 sand in 423 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2539 psi w/ ave rate of 23.4 BPM. ISIP 2646 psi. Actual Flush: 4624 gals.

Updated Rod & Tubing detail.
Convert to Injection Well
Conversion MIT Finalized – update tbg detail

PERFORATION RECORD

4710-4724'	4 JSPF	56 holes
4824-4839'	4 JSPF	60 holes
4944-4954'	4 JSPF	40 holes
5094-5109'	4 JSPF	60 holes
5203-5211'	4 JSPF	32 holes
5571-5592'	4 JSPF	84 holes
5606-5620'	4 JSPF	56 holes

NEWFIELD

State 3-16-9-16
 660' FNL & 1990' FWL
 NE/NW Section 16-T9S-R16E
 Duchesne Co, Utah
 API #43-013-33847; Lease #Utah State ML-16532

PBTD @ 5812'
 TD @ 5855'

Spud Date: 4/1/08
 Put on Production: 6/3/08
 GL: 5881' KB: 5893'

State 4-16-9-16

Injection Wellbore
DiagramSURFACE CASING


CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7jts (300.96')
 DEPTH LANDED: 312.81' KB
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 1- 160, sxs Class "G" cmt, est 6 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 158jts 5819.28
 HOLE SIZE: 7-7/8"
 DEPTH LANDED: 5832.53'
 CEMENT DATA: 300 sx Premilite II and 400 sx 50/50 Poz
 CEMENT TOP AT: 48'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 150 jts (4709.9')
 SEATING NIPPLE: 2-7/8" (1.10')
 SN LANDED AT: 4721.9' KB
 ON/OFF TOOL AT: 4723'
 ARROW #1 PACKER CE AT: 4727.62'
 XO 2-3/8 x 2-7/8 J-55 AT: 4731.7'
 TBG PUP 2-3/8 J-55 AT: 4732.2'
 X/N NIPPLE AT: 4736.3'
 TOTAL STRING LENGTH: EOT @ 4737.94'

FRAC JOB

05-28-08 5209-5228' **Frac LODC sds as follows:** 200,061# 20/40 sand in 1373 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1997 psi w/ ave rate of 27.3 BPM. ISIP 2322 psi. Actual Flush: 4683 gals.

05-28-08 5108-5114' **Frac A1 & A3 sds as follows:** 120,424# 20/40 sand in 868 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1922 psi w/ ave rate of 27.0 BPM. ISIP 2220 psi. Actual Flush: 4616 gals.

05-28-08 4916-4925' **Frac B1 sds as follows:** 54,952# 20/40 sand in 495 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1767 psi w/ ave rate of 23.4 BPM. ISIP 1705 psi. Actual Flush: 4406 gals.

05-28-08 4842-4856' **Frac C sds as follows:** 115,003# 20/40 sand in 846 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1920 psi w/ ave rate of 23.5 BPM. ISIP 1926 psi. Actual Flush: 4330 gals.

05-28-08 4778-4791' **Frac D3 sds as follows:** 115,003# 20/40 sand in 846 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1920 psi w/ ave rate of 23.5 BPM. ISIP 1926 psi. Actual Flush: 4679 gals.

3/28/09 **Pump Change.** Updated r & t details.

6/5/09 **Pump Change.** Updated rod & tubing details.

07/02/13 **Convert to Injection Well**

07/03/13 **Conversion MIT Finalized** – update tbg detail

PERFORATION RECORD

4778-4791'	4 JSPF	52 holes
4842-4856'	4 JSPF	56 holes
4916-4925'	4 JSPF	36 holes
5108-5114'	4 JSPF	24 holes
5126-5132'	4 JSPF	24 holes
5198-5203'	4 JSPF	20 holes
5209-5228'	4 JSPF	76 holes

NEWFIELD

State 4-16-9-16
 660' FNL & 815' FWL
 NW/NW Section 16-T9S-R16E
 Duchesne Co, Utah
 API #43-013-33848; Lease #Utah State ML-16532

Spud Date: 03-03-08

Put on Production: 05-12-08

GL: 5876' KB: 5888'

State 6-16-9-16

Injection Wellbore
DiagramSURFACE CASING


CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 10 jts. (321.48')
 DEPTH LANDED: 431'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 205 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 137 jts. (5809.35')
 HOLE SIZE: 7-7/8"
 DEPTH LANDED: 5822.6'
 CEMENT DATA: 300 sk Prem. Lite II mixed & 400 sxs 50/50 POZ.
 CEMENT TOP AT: 38'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 133 jts (4030')
 SEATING NIPPLE: 2-7/8" N-80 (1.10')
 SN LANDED AT: 4042' KB
 RET TOOL N-80 AT: 4043.1'
 ARROW #1 PACKER CE AT: 4050.1'
 XO 2-3/8 x 2-7/8 J-55 AT: 4053.1'
 TBG PUP 2-3/8 J-55 AT: 4053.6'
 X/N NIPPLE AT: 4057.7'
 TOTAL STRING LENGTH: EOT @ 4059.27

FRAC JOB

4-29-08 5548-5574' **Frac CP1 sands as follows:**
 Frac with 125681 #'s of 20/40 sand in 903 bbls of Lightning 17 fluid. Treat at an ave pressure of 1713 psi @ 23.9 BPM. ISIP 2198 psi.

4-29-08 5086-5094' **Frac A1 sands as follows:**
 Frac with 60763 #'s of 20/40 sand in 507 bbls of Lightning 17 fluid. Treat at an ave pressure of 2229 psi @ 23.2 BPM. ISIP 2405psi.

4-29-08 4692-4748' **Frac D3 & D2 sands as follows:**
 Frac with 133141 #'s of 20/40 sand in 962 bbls of Lightning 17 fluid. Treat at an ave pressure of 2005 psi @ 24.6 BPM. ISIP 2005 psi.

4-29-08 4093-4171' **Frac GB4 & GB6 sand as follows:**
 Frac with 43849 #'s of 20/40 sand in 426 bbls of Lightning 17 fluid. Treat at an ave pressure of 1908 psi @ 23.2 BPM. ISIP 1900 psi.

7/14/08 **Pump change.** Updated tubing and rod detail.

9/9/08 **Pump Change.** Updated rod & tubing details.

3/23/10 **Pump change.** Updated rod and tubing detail.

1/26/12 **Parted rods.** Updated rod and tubing detail.

07/18/13 **Convert to Injection Well**

07/18/13 **Conversion MIT Finalized** -- update tbg detail

PERFORATION RECORD

4093-4099'	4 JSPF	24 holes
4125-4130'	4 JSPF	20 holes
4166-4171'	4 JSPF	20 holes
4692-4708'	4 JSPF	64holes
4732-4748'	4 JSPF	64 holes
5086-5094'	4 JSPF	32 holes
5548-5574'	4 JSPF	104 holes



State 6-16-9-16
 1847' FNL & 1974' FWL
 SENW Section 16-T9S-R16E
 Duchesne Co, Utah
 API #43-013-33850; Lease # Utah State ML-16532

FEDERAL 14-9-9-16

Spud Date: 03/20/07
 Put on Production: 05/15/07
 GL: 5814' KB: 5826'

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7jts (311.85')
 DEPTH LANDED: 321.85'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 160sxs Class "G", circ. 5 bbls to surf.

PRODUCTION CASING


CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 137jts (6072.44')
 DEPTH LANDED: 6070.44'
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 300 sxs Premlite II & 450 sxs 50/50 POZ.
 CEMENT TOP: 103' per CBL 4/18/07

TUBING (KS 11/28/12)

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 185jts (5833.4')
 TUBING ANCHOR: 5845.4'
 NO. OF JOINTS: 1jt (31.6')
 SEATING NIPPLE: 2-7/8" (1.10')
 SN LANDED AT: 5879.8'
 NO. OF JOINTS: 1jt (31.6')
 NOTCHED COLLAR: 2-7/8" (0.5')
 TOTAL STRING LENGTH: EOT @ 5913'

SUCKER RODS (KS 11/28/12)

POLISHED ROD: 26' x 1-1/2" Polished Rod
 SUCKER RODS: 99 x 3/4" 4per Guided Rods, 111 x 3/4" Sucker Rods, 18 x 3/4" 4per Guided Rods, 6 x 1-1/2" Sinker Bars
 PUMP SIZE: CDI 2-1/2" x 1-1/2" x 12' x 16' RHAC
 STROKE LENGTH: 86"
 PUMP SPEED, SPM: 3.9
 PUMPING UNIT: AMERICAN C-228-246-86

FRAC JOB

05/07/07	5869-5886'	Frac CP4 sands as follows: 58920# 20/40 sand in 518 bbls Lightning 17 frac fluid.
05/07/07	5600-5610'	Frac CP1 sands as follows: 24630# 20/40 sand in 362 bbls Lightning 17 frac fluid.
05/08/07	5354-5388'	Frac LODC sands as follows: 59848# 20/40 sand in 500 bbls Lightning 17 frac fluid.
05/08/07	5223-5234'	Frac A3 sands as follows: 29710# 20/40 sand in 343 bbls Lightning 17 frac fluid.
05/08/07	5140-5150'	Frac A1 sands as follows: 45023# 20/40 sand in 417 bbls Lightning 17 frac fluid.
05/08/07	4985-4990'	Frac B2 sands as follows: 49798# 20/40 sand in 438 bbls Lightning 17 frac fluid.
05/08/07	4870-4979	Frac C sands as follows: 19413# 20/40 sand in 293 bbls Lightning 17 frac fluid.
05/08/07	4752-4800	Frac D3 & D2 sands as follows: 90249# 20/40 sand in 1959 bbls Lightning 17 frac fluid.
05/08/07	4148-4232	Frac GB6 & GB4 sands as follows: 40824# 20/40 sand in 382 bbls Lightning 17 frac fluid.
05/23/08		updated rod and tubing detail
03/12/11		Parted Rods. Rod & tubing details updated

PERFORATION RECORD

04/18/07	5869-5886'	4 JSPF	68 holes
05/07/07	5600-5610'	4 JSPF	40holes
05/07/07	5379-5388'	4 JSPF	36 holes
05/08/07	5354-5362'	4 JSPF	32 holes
05/08/07	5223-5234'	4 JSPF	44 holes
05/08/07	5140-5150'	4 JSPF	40 holes
05/08/07	4985-4990'	4 JSPF	20 holes
05/08/07	4972-4979'	4 JSPF	28 holes
05/08/07	4870-4880'	4 JSPF	40 holes
05/08/07	4790-4800'	4 JSPF	40 holes
05/08/07	4752-4765'	4 JSPF	52 holes
05/08/07	4219-4232'	4 JSPF	52 holes
05/08/07	4148-4154'	4 JSPF	24 holes

NEWFIELD

FEDERAL 14-9-9-16

718'FSL & 1976' FWL

SE/SW Section 9-T9S-R16E

Duchesne Co, Utah

API #43-013-33053; Lease # UTU-79831

KS 11/28/12

Spud Date: 03/27/07
 Put on Production: 05/18/07
 GL:5788' KB:5800'

FEDERAL 15-9-9-16

Injection Wellbore
DiagramSURFACE CASING

CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7 jts. (312.28')
 DEPTH LANDED: 324.13' KB
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 160 sxs Class "G" cmt, est 6 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 139 jts. (6038.30')
 DEPTH LANDED: 6051.55' KB
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 300 sxs Prem. Lite II mixed & 450 sxs 50/50 POZ.
 CEMENT TOP: 52'

TUBING

SIZE/GRADE/WT.: 2-7/8" / 6.5# / J-55
 NO. OF JOINTS: 128 jts (4012.5')
 SEATING NIPPLE: 2-7/8" (1.10')
 SN LANDED AT: 4024.5'
 ON/OFF TOOL AT: 4025.6'
 ARROW #1 PACKER CE AT: 4030'
 XO 2-3/8 x 2-7/8 J-55 AT: 4034.4'
 TBG PUP 2-3/8 J-55 AT: 4034.9'
 X/N NIPPLE AT: 4041.2'
 TOTAL STRING LENGTH: EOT @ 4043'

FRAC JOB

05/09/07 5653-5664' **Frac CP2 sands as follows:**
 19973# 20/40 sand in 326 bbls Lightning 17
 frac fluid. Treated @ avg press of 1977 psi
 w/avg rate of 24.7 BPM. ISIP 1722 psi. Calc
 flush: 5651 gal. Actual flush: 5166 gal.

05/14/07 5566-5580' **Frac CP.5 sands as follows:**
 45412# 20/40 sand in 433 bbls Lightning 17
 frac fluid. Treated @ avg press of 1956 psi
 w/avg rate of 24.7 BPM. ISIP 1956 psi. Calc
 flush: 5564 gal. Actual flush: 5122 gal.

05/14/07 5286-5292' **Frac LODC sands as follows:**
 19538# 20/40 sand in 300 bbls Lightning 17
 frac fluid. Treated @ avg press of 2539 psi
 w/avg rate of 24.8 BPM. ISIP 2675 psi. Calc
 flush: 5284 gal. Actual flush: 4830 gal.

05/14/07 5144-5154' **Frac A3 sands as follows:**
 45178# 20/40 sand in 423 bbls Lightning 17
 frac fluid. Treated @ avg press of 1893 psi
 w/avg rate of 24.8 BPM. ISIP 2111 psi. Calc
 flush: 5142 gal. Actual flush: 4662 gal.

05/14/07 4750-4780' **Frac D2 sands as follows:**
 60592# 20/40 sand in 489 bbls Lightning 17
 frac fluid. Treated @ avg press of 1606 psi
 w/avg rate of 24.8 BPM. ISIP 1847 psi. Calc
 flush: 4748 gal. Actual flush: 4284 gal.

05/14/07 4230-4248' **Frac GB6 sands as follows:**
 92270# 20/40 sand in 664 bbls Lightning 17
 frac fluid. Treated @ avg press of 1955 psi
 w/avg rate of 24.8 BPM. ISIP 2175 psi. Calc
 flush: 4228 gal. Actual flush: 4116 gal.


9-5-07 Pump Change. Updated rod & tubing details.
 12-13-07 Pump Change. Updated rod & tubing details.
 6/27/2011 Pump Change. Updated rod & tubing details

10/22/12 4058-4064' **Frac GB2 sands as follows:**
 24437# 20/40 sand in 272 bbls Lightning 17
 frac fluid.

10/24/12 **Convert to Injection Well**
 10/25/12 **Conversion MIT Finalized** - update tbg
 detail

PERFORATION RECORD

05/09/07	5653-5664'	4 JSPF	44 holes
05/14/07	5566-5580'	4 JSPF	56 holes
05/14/07	5286-5292'	4 JSPF	24 holes
05/14/07	5144-5154'	4 JSPF	40 holes
05/14/07	4774-4780'	4 JSPF	24 holes
05/14/07	4750-4756'	4 JSPF	24 holes
05/14/07	4230-4248'	4 JSPF	72 holes
10/20/12	4058-4064'	3 JSPF	18 holes



NEWFIELD

FEDERAL 15-9-9-16

731' FSL & 1804' FEL
 SW/SE Section 9-T9S-R16E
 Duchesne Co, Utah
 API #43-013-33054; Lease # UTU-79831

Spud Date: 3/26/82

Put on Production: 9/8/82

GL: 5825' KB: 5835'

Castle Peak 32-16-9-16

Injection Wellbore
DiagramSURFACE CASING

CSG SIZE: 8-5/8"

GRADE: K-55

WEIGHT: 24#

LENGTH: 6 jts (214' FC)

DEPTH LANDED: 255' Shoe

HOLE SIZE: 12-1/4"

CEMENT DATA: 200 sxs Class "G", circ 60 sxs to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: K-55

WEIGHT: 15 5#

LENGTH: 141 jts (5561' FC)

DEPTH LANDED: 5650' Shoe

HOLE SIZE: 7-7/8"

CEMENT DATA: 260 sx 50/50 poz,

CEMENT TOP: 4480' per CBL 8/5/82

TUBING

SIZE/GRADE/WT : 2-7/8" / J-55 / 6 5#

NO. OF JOINTS: 149 jts (4625.3')

SEATING NIPPLE: 2-7/8" (1.10')

SN LANDED AT: 4637.3' KB

ON/OFF TOOL AT: 4638.4'

ARROW #1 PACKER CE AT: 4644'

XO 2-3/8 x 2-7/8 J-55 AT: 4647.9'

TBG PUP 2-3/8 J-55 AT: 4648.4'

X/N NIPPLE AT: 4652.5'


TOTAL STRING LENGTH: EOT @ 4654.14'

FRAC JOB

8/5/82	5504-5512', 5526-5554'	Acidized w/2000 gal. 15% HCl w/1000 gal. terasperse, 20 gal. FE-1A & 4 gal. HAL-75 inhibitor. Fraced w/42000 gal. VER-1400 gelled H2O w/62500# 20/40 sand & 10000# 10/20 sand.
8/6/82	5000-5010', 4732-4738'	Fraced w/25000 gal. VER-1400 gelled H2O w/28000# of 20/40 sand & 10000# of 10/20 sand
02/07/14		Convert to Injection Well
02/07/14		Conversion MIT Finalized - update tbg detail

PERFORATION RECORD

8/6/82	4732-4738'	2 JSPF	12 holes
8/6/82	5000-5010'	2 JSPF	20 holes
8/5/82	5504-5512'	2 JSPF	16 holes
8/5/82	5526-5554'	2 JSPF	28 holes

**NEWFIELD**

Castle Peak State 32-16-9-16
2009' FNL & 1838' FEL
SW/NE Section 16-T9S-R16E
Duchesne County, Utah
API #43-013-30650; Lease #ML-16532

Spud Date: 3/29/08
 Put on Production: 5/21/08
 GL: 5776' KB: 5788'

State 1-16-9-16

Injection Wellbore
DiagramSURFACE CASING

CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7 jts
 DEPTH LANDED: 323.67
 HOLE SIZE: 12-1/4"
 CEMENT DATA: To surface with 160 sx Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 152 jts
 HOLE SIZE: 7-7/8"
 DEPTH LANDED: 5835'
 CEMENT DATA: 300 sx Prem. Lite II & 425 sxs 50/50 POZ.
 CEMENT TOP AT: 90'

TUBING


SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
 NO. OF JOINTS: 130 jts (4081')
 SEATING NIPPLE: 2-7/8" N-80 (1.10')
 SN LANDED AT: 4093' KB
 ON/OFF TOOL AT: 4094.1'
 ARROW #1 PACKER CE AT: 4100.4'
 XO 2-3/8 x 2-7/8 J-55 AT: 4104.1'
 TBG PUP 2-3/8 J-55 AT: 4104.6'
 X/N NIPPLE AT: 4108.7'
 TOTAL STRING LENGTH: EOT @ 4110.27'

FRAC JOB

05-15-08	5549-5556'	Frac CPI sds as follows: 19,592# 20/40 sand in 324 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2457 psi @ ave rate of 23.1 BPM. ISIP 1720 psi. Actual Flush: 5040 gals.
05-15-08	5200-5211'	Frac LODC sds as follows: 44,487# 20/40 sand in 448 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2174 psi @ ave rate of 23.4 BPM. ISIP 2560 psi. Actual Flush: 4696 gals.
05-15-08	5086-5096'	Frac A1 sds as follows: 45,335# 20/40 sand in 439 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1987 psi @ ave rate of 23.3 BPM. ISIP 2240 psi. Actual Flush: 4578 gals.
05-15-08	4938-4944'	Frac B2 sds as follows: 20,020# 20/40 sand in 310 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2133 psi @ ave rate of 23.2 BPM. Pumped 504 gals of 15% HCL in flush for Stage #5. ISIP 1885 psi. Actual Flush: 4431 gals.
05-15-08	4762-4768'	Frac D3 sds as follows: 20,619# 20/40 sand in 307 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1898 psi @ ave rate of 23.4 BPM. Pumped 504 gals of 15% HCL in flush for Stage #6. ISIP 2099 psi. Actual Flush: 4255 gals.
05-15-08	4155-4165'	Frac GB4 & GB6 sds as follows: 91,335# 20/40 sand in 664 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1983 psi @ ave rate of 23.3 BPM. ISIP 1900 psi. Actual Flush: 4078 gals.
2/19/09		Pump Change. Updated r & t details.
9/17/09		Tubing Leak. Updated rod & tubing details.
11/19/09		Pump Change. Updated rod & tubing.
6/14/2010		Tubing Leak. Update rod and tubing details
03/25/11		Pump Change. Rod & tubing updated.
07/11/13		Convert to Injection Well
07/15/13		Conversion MIT Finalized – update tbg detail

PERFORATION RECORD

4130-4142'	4 JSPF	48 holes
4155-4165'	4 JSPF	40 holes
4762-4768'	4 JSPF	24 holes
4938-4944'	4 JSPF	24 holes
5086-5096'	4 JSPF	40 holes
5200-5211'	4 JSPF	44 holes
5549-5556'	4 JSPF	28 holes

**NEWFIELD****State 1-16-9-16**

687' FNL & 831' FEL

NE/NE Section 16-T9S-R16E

Duchesne Co, Utah

API #43-013-33845; Lease #Utah State ML-16532

LCN 07/22/13

NEWFIELD**GMBU T-9-9-16**

Greater Monument Butte - Duchesne County, Utah, USA

Surface Location: SW/SW - Sec 10, T9S, R10E; 571' FSL & 621' FWL

Elevation: 5743' GL + 10' KB


APW: 43-013-51148; Lease#: UTU-72107

Mickey Moulton

DLB 5/8/13

Spud Date: 10/5/12; PoP Date: 1/21/13

CASING DETAIL	Casing	Top	Bottom	Size	Wt	Grade	Drift	Burst	Collapse	ID	bb/ft	Coupling	Hole
	Surf	10'	320'	8.625	24#	J-55	7.972"	2,950	1,370	8.097"	2.6749	STC	12.250
	Prod	10'	6,422'	5.500	15.5#	J-55	4.825"	4,810	4,040	4.950"	0.9997	LTC	7.875
TBC DETAIL	Top	Bottom	Coupling	Size	Wt.	Grade	Drift	Burst	Collapse	ID	Packer/Hanger		
	10'	5,512'	8EUE	2-7/8"	6.5#	J-55	2.347"	7,260	7,680	2.441"	Tubing Anchor Set @ 5,416'		
ROD DETAIL	Component			Top	Bottom	Size	Grade	Length	Count	Pump			
	4per Guided Rod				30'	1 1/4"	C(API)	30'	1	Insert Pump: 2.5 Max ID x 1.75 Plunger RHAC @ 5,440'			
	Pony Rod			30'	32'	7/8"	C(API)	2'	1				
	Polish Rod			32'	40'	7/8"	C(API)	8'	1				
	4per Guided Rod			40'	1,840'	7/8"	Tenaris D78	1,800'	72				
	4per Guided Rod			1,840'	4,740'	3/4"	Tenaris D78	2,900'	116				
	8per Guided Rod			4,740'	5,440'	3/4"	Tenaris D78	700'	28				
Stage	Top	Bottom	SPF	EHD	Date	Frac Summary							
4	4,274'	4,276'	3	0.34	1/8/2013	Formation:	GB-4						
	4,281'	4,283'	3	0.34	1/8/2013	20/40 White:	61,226 lbs	15% HCl:	0 gals				
	4,289'	4,291'	3	0.34	1/8/2013	Pad:	1,789 gals	Treating Fluid:	13,563 gals				
						Flush:	4,255 gals	Load to Recover:	19,607 gals				
						ISIP=	0.902 psi/ft	Max STP:	2,287 psi				
3	4,972'	4,973'	3	0.34	1/8/2013	Formation:	B-1 C-Sand						
	4,982'	4,984'	3	0.34	1/8/2013	20/40 White:	53,857 lbs	15% HCl:	504 gals				
	5,071'	5,073'	3	0.34	1/8/2013	Pad:	1,865 gals	Treating Fluid:	12,697 gals				
	5,081'	5,083'	3	0.34	1/8/2013	Flush:	4,969 gals	Load to Recover:	20,035 gals				
						ISIP=	0.896 psi/ft	Max STP:	3,217 psi				
2	5,130'	5,132'	3	0.34	1/8/2013	Formation:	A-3 B-3						
	5,260'	5,262'	3	0.34	1/8/2013	20/40 White:	74,900 lbs	15% HCl:	1,823 gals				
	5,281'	5,282'	3	0.34	1/8/2013	Pad:	3,251 gals	Treating Fluid:	15,162 gals				
	5,298'	5,300'	3	0.34	1/8/2013	Flush:	5,641 gals	Load to Recover:	25,877 gals				
						ISIP=	0.900 psi/ft	Max STP:	2,886 psi				
1	5,407'	5,409'	3	0.34	1/8/2013	Formation:	LODC						
	5,420'	5,422'	3	0.34	1/8/2013	20/40 White:	370,555 lbs	15% HCl:	714 gals				
	5,436'	5,438'	3	0.34	1/8/2013	Pad:	4,070 gals	Treating Fluid:	9,549 gals				
						Flush:	4,712 gals	Load to Recover:	18,835 gals				
						ISIP=	N/A psi/ft	Max STP:	3,359 psi				
CEMENT	Surf	On 10/6/12 Baker cemented 8 5/8" casing w/ 160 sks Class "G" + 2% KCl + 0.25#/sk Cello Flake at 15.8 ppg w/ 1.17 yield and returned 5bbls to the pit.											
	Prod	On 10/17/2012 Baker pumped 470 sks lead @ 11 ppg w/ 3.53 yield plus 240 sks tail @ 14.4 ppg w/ 1.24 yield. Returned 25bbls to the pit. TOC @ 1'.											



EOT @ 5512'; TA @ 5416'

5-1/2" Shoe @ 6422'

PBTD @ 6398'

TVD @ 6269'

BHST = 190°F

MD @ 6425'

Spud Date: 5-4-98
Put on Production: 6-29-98
GL: 5757.4' KB: 5767.4'

S. Wells Draw #16-9-9-16

Wellbore Diagram

Initial Production: 89 BOPD,
102 MCFD, 7 BWPD

SURFACE CASING

SIZE: 8 5/8"
GRADE: J-55
WEIGHT: 24 #
LENGTH: 8 jts @ 292.44'
HOLE SIZE: 12 1/4"
DEPTH LANDED: 292.94'
CEMENT DATA: 120 sx Premium Plus, est 6 bbls cmt to surface

PRODUCTION CASING

SIZE: 5 1/2"
GRADE: J-55
WEIGHT: 15.5 #
LENGTH: 137 jts @ 5824'
HOLE SIZE: 7 7/8"
DEPTH LANDED: 5835'
CEMENT DATA: 360 sx 28:72 Poz &
375 sx Class G
CEMENT TOP AT: surface

TUBING RECORD

SIZE/GRADE/WT.: 2 7/8", M-50
NO. OF JOINTS: 168 jts. (5199.0')
TUBING ANCHOR: 5199.0'
NO. OF JOINTS: 2 jts. (59.3')
SEATING NIPPLE: 2 7/8" (1.10")
SN LANDED AT: 5261.1'
NO. OF JOINTS: 2 jts (62.6')
TOTAL STRING LENGTH: EOT @ 5325'

SUCKER RODS

POLISHED ROD: 1 - 22' x 1 1/2"
SUCKER RODS: 1-6' x 3/4" pony rod, 2- 8' x 3/4" pony rods, 95- 3/4" guided rods, 86- 3/4" guided rods, 25- 3/4" guided rods, 4- 1 1/2" weight bars
PUMP SIZE: 2 1/2" x 1 1/2" x 12' x 15' RHAC
STROKE LENGTH: 124"
PUMP SPEED, SPM: ?

FRAC JOB

6-19-98 5110'-5246' **Frac A/LDC sand as follows:**
77,000# 20/40 sand in 467 bbls Viking.
Perfs broke @ 3260 psi. ISIP-3740 psi.
5 min 3120 psi. Flowback on 12/64"
ck for 3 hrs & died.

6-21-98 4857'-4863' **Frac C sand as follows:**
54,400# 20/40 sand in 260 bbls Viking.
Perfs broke @ 2385 psi. Treated w/avg
press of 2000 psi w/avg rate of 29 BPM.
Screened out.

6-24-98 4698'-4704' **Frac D sand as follows:**
104,000# 20/40 sand in 436 bbls Viking.
Perfs broke @ 3520 psi. Treated w/avg
press of 2310 psi w/avg rate of 25.4 BPM.
ISIP-2310 psi. 5 min 2150 psi. Flowback
on 12/64" ck for 4 hrs & died.


6-26-98 4149'-4224' **Frac GB sand as follows:**
108,354# 20/40 sand in 646 bbls Viking.
Perfs broke @ 2710 psi. Treated w/avg
press of 1770 psi w/avg rate of 26 BPM.
ISIP-2350 psi, 5 min 2050 psi. Flowback
on 12/64" ck for 4 hrs & died.

9/7/07 Tubing Leak. Updated rod & tubing details.

9/20/2010 Tubing leak. Updated rod and tubing detail.

PERFORATION RECORD

6-18-98	5110'-5112'	4 JSPF	8 holes
6-18-98	5138'-5140'	4 JSPF	8 holes
6-18-98	5240'-5246'	4 JSPF	8 holes
6-20-98	4857'-4863'	4 JSPF	8 holes
6-23-98	4698'-4704'	4 JSPF	24 holes
6-25-98	4149'-4153'	4 JSPF	16 holes
6-25-98	4161'-4165'	4 JSPF	16 holes
6-25-98	4207'-4209'	4 JSPF	8 holes
6-25-98	4219'-4224'	4 JSPF	20 holes



S. Wells Draw #16-9-9-16

696 FSL 744 FEL

SESE Section 9-T9S-R16E

Duchesne Co, Utah

API #43-013-32044; Lease #U-40894

S. Wells Draw 13-10-9-16

Spud Date: 8/15/98
Put on Production: 9/16/98
GL: 5738' KB: 5748' (10' KB)

Initial Production: 12 BOPD,
86 MCFD, 2 BWPD

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts.(294')
DEPTH LANDED: 304'KB
HOLE SIZE: 12-1/4"
CEMENT DATA: 140 sx Premium cmt & 45 sx
Class "G", est 7 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 136 jts. (5834')
SET AT: 5843' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 280 sx Premium modified mixed & 300 sx class "G"
CEMENT TOP AT: Surface per cement bond log(Schlumberger)

TUBING

SIZE/GRADE/WT: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 139 jts (4291.5')
SEATING NIPPLE: 2-7/8"
SN LANDED AT: 4301.5' KB
CE @ 4305.8'
TOTAL STRING LENGTH: EOT @ 4306' KB

Injection Wellbore Diagram


CEMENT TOP AT:
Surface per CBL

FRAC JOB

9/11/98 4836'-4972' **Frac B-1 & B-2 sand as follows:**
112,100# 20/40 sand in 548 bbls Viking I-25. Perfs broke @ 3118 psi @ 21 BPM. Treated w/avg press of 2080 psi w/avg rate of 30.4 BPM. ISIP-2300 psi, 5 min 2180 psi. Flowback on 12/64" ck for 3.5 hrs & died.

9/13/98 4416'-4428' **Frac PB-10 sand as follows:**
8,220# 20/40 sand in 66 bbls Viking I-25 fluid. Perfs broke @ 3990 psi. Treated w/avg press of 2220 psi w/avg rate of 12.6 BPM. ISIP-1600 psi, 5 min 1485 psi. Flowback on 12/64" ck for 1 hr & died.

04/06/12 **Convert to Injection Well**
04/10/12 **Conversion MIT Finalized -- update tbg detail**



PERFORATION RECORD

9/9/98	4836'-4840'	4 JSPF	16 holes
9/9/98	4933'-4936'	4 JSPF	12 holes
9/9/98	4958'-4964'	4 JSPF	24 holes
9/9/98	4966'-4972'	4 JSPF	24 holes
9/9/98	4416'-4428'	4 JSPF	48 holes

NEWFIELD

S. Wells Draw 13-10-9-16

610 FSL 632 FWL

SWSW Section 10-T9S-R16E

Duchesne Co, Utah

API #43-013-32047; Lease #UTU-72107

GMB 3-16-9-16H

Wellbore Diagram



Surface Location: NE/NW, Sec 16, T9S R16E
County/State: Greater Monument Butte, Duchesne County, Utah
Elevation: 5847' GL + 12' KB
API: 43-013-50441

Wellhead		Casing Detail		Size	Wt.	Grade	Conn.	Top	Bottom	Burst	Collapse	ID	Drift	bbf/ft	Hole	TOC
8-5/8" Casing Shoe 1,025		Surface		8-5/8"	24#	J-55	LTC	0	1,025							Surface
		Production		5-1/2"	17#	M-80	LTC	0	5,993	7,740	7,020	4,892	4,767	0.0233	7-7/8"	Port Collar
		Production		4-1/2"	11.6#	P-110	LTC	5,993 TVD	10,249 6,011	7,774	8,510	4,000	3,875	0.0155	6-1/8"	5,654' md to Surface

burst & collapse values are book, no additional safety factors have been applied

Tubing Detail	Size	Wt.	Grade	Conn.	Length	Top	Bottom	Joints
TBG DETAIL: sand drain valve, 3 jts 2 7/8" tbgs., Cavins De-sander, 2 7/8" sub, 1 jt 2 7/8" tbgs., SN, 1 jt 2 7/8" tbgs., 5 1/2" TAC, 187 jts 2 7/8" tbgs and tbgs hanger. TA @ 5,870'. SN @ 5,903'. EOT @ 6,052' NOTE on Tubing Anchor: TA (shortened inner springs & beveled outer springs -4.625" OD)								

WELLBORE FLUIDS
Lateral section fluid: +8.4 ppg "clean" brine

Rod Detail	Size	Grade	Count	Length	Top	Bottom
Pump and Rod Detail: Weatherford MacGyver 1 3/4" x 28' rod pump, stabilizer sub, on/off tool, stabilizer sub, SE 4 Co-rod, 1- 8', 6', 4', 2' x 7/8" pony rods, 1 1/2" x 28' polished rod NOTE on Pump: with CoRod, must have Clutch (on/off tool) installed.						

Proposed Frac Data		Top	Bottom	Packers Plus 12 Stage StackFrac HD Stimulation Liner								Prop type/size	Prop Vol (lbs)	Total Clean Vol (bbls)
Toe Section		10,249	10,249	Packers Plus 4-1/2" Toe Circulating Sub w/1,000" Seat for 1,250" SF2 High Pressure Ball (Actuated at 1,098 psi). And Open Hole TD										
Stage 1		10,067	10,249	Dual Hydraulic Frac Ports								100 mesh sand	0	
OH AnchorPacker		10,060	10,067	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								30/50 mesh sand	0	1,803
Mechanical Packer 1		10,002	10,002	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								100 mesh sand	34,144	2,342
Stage 2		9,882	10,002	FracPort 2:								30/50 mesh sand	30,780	
Mechanical Packer 2		9,877	9,882	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								100 mesh sand	38,388	2,775
Stage 3		9,814	9,877	FracPort 3:								30/50 mesh sand	18,833	
Mechanical Packer 3		9,354	9,354	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								100 mesh sand	7,548	2,776
Stage 4		9,036	9,354	FracPort 4:								30/50 mesh sand	0	
Mechanical Packer 4		9,036	9,036	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								100 mesh sand	26,377	4,118
Stage 5		8,710	9,036	FracPort 5:								30/50 mesh sand	36,321	
Mechanical Packer 5		8,705	8,710	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								100 mesh sand	37,277	3,907
Stage 6		8,386	8,705	FracPort 6:								30/50 mesh sand	30,591	
Mechanical Packer 6		8,381	8,386	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								100 mesh sand	33,228	2,784
Stage 7		8,066	8,381	FracPort 7:								30/50 mesh sand	21,643	
Mechanical Packer 7		8,061	8,066	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								100 mesh sand	35,076	3,706
Stage 8		7,743	8,061	FracPort 8:								30/50 mesh sand	30,426	
Mechanical Packer 8		7,738	7,743	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								100 mesh sand	30,309	2,777
Stage 9		7,418	7,738	FracPort 9:								30/50 mesh sand	14,314	
Mechanical Packer 9		7,413	7,418	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								100 mesh sand	25,505	1,889
Stage 10		6,788	7,413	FracPort 10:								30/50 mesh sand	3,487	
Mechanical Packer 10		7,089	7,089	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								100 mesh sand	37,884	2,804
Stage 11		6,788	7,089	FracPort 11:								30/50 mesh sand	30,649	
Mechanical Packer 11		6,783	6,788	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)								100 mesh sand	31,284	2,735
Stage 12		6,445	6,783	FracPort 12:								30/50 mesh sand	21,198	
Mechanical Packer 12		6,438	6,445	Packer Plus 7" x 4-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,268psi)										Total Fluid
OH AnchorPacker		6,451	6,458	Packer Plus 8-5/8" x 5-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,046psi)										34,456
Rockseal II Packer		6,372	6,377	Packer Plus 8-5/8" x 5-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,046psi)										(bbl)
Lat Length			3,804									Sand Total	335,921	
Total Stim. Lateral			3,804									580,309	244,388	
Avg. Stage Length			317	*between packers								# sand per foot of lateral	153	

LP MAX 30 6,993

12

11

10

9

8

7

6

5

4

3


2

1

MD TD 10,259
TVD 6,011

Liner Length: 10,249'
Liner: 5-1/2" 17# / 4-1/2" 11.6# M/N80 LTC
Top Packer: 9-5/8" x 5-1/2" RockSeal II / IIS
Set @ 5,372'

FINAL COMPLETION



Casing	Start	End	FTG
8-5/8" 24# J55 LTC	0'	1,025'	1,025'
Liner	Start	End	FTG
5-1/2" 17# M80	0'	5,993'	5,993'
4-1/2" 11.6# N80	5,993'	10,249'	4,256'

RockSeal Packers @

ANCH	10,080'	PKR 8	7,738'
PKR 1	10,002'	PKR 9	7,413'
PKR 2	9,677'	PKR 10	7,088'
PKR 3	9,354'	PKR 11	6,763'
PKR 4	9,030'	PKR 12	6,438'
PKR 5	8,705'		
PKR 6	8,381'	ANCH	5,451'
PKR 7	8,061'	PKR 13	5,372'

Interval Spacing

STG 1	179'	Toe
STG 2	324'	
STG 3	324'	
STG 4	324'	
STG 5	325'	
STG 6	324'	
STG 7	320'	
STG 8	322'	
STG 9	325'	
STG 10	325'	
STG 11	326'	
STG 12	325'	EOB

AVG 324'

Marker Joint 4,743'

KOP @ 5,400'

Port Collar 5,355'

Top Packer @ 5,372'

5-1/2"x4-1/2" Crossover @ 5,993'

FracPorts @

DEH	10,160'	2.625	8,220'
2.000	9,841'	2.750	7,901'
2.125	9,517'	2.875	7,577'
2.250	9,193'	3.000	7,252'
2.375	8,869'	3.125	6,927'
2.500	8,544'	3.250	6,601'

EOB @ 6,039'

In Zone @ 6,400'

TD @ 10,259'

GS @ 10,249'



NEWFIELD



Schematic

43-013-51448

Well Name: GMBU G-16-9-16


Surface Legal Location SWNW 2081 FNL 759 FWL Sec 16 T9S R16E				API/UWI 43013514480000	Well RC 500343049	Lease ML-16532	State/Province Utah	Field Name GMBU CTB3	County Duchesne
Spud Date 11/5/2013	Rig Release Date 11/23/2013	On Production Date	Original KB Elevation (ft) 5,931	Ground Elevation (ft) 5,921	Total Depth All (TVD) (ftKB) Original Hole - 6,140.5	PBTD (All) (ftKB) Original Hole - 6,284.4			

Most Recent Job

Job Category Initial Completion	Primary Job Type Fracture Treatment	Secondary Job Type P&P	Job Start Date 12/17/2013	Job End Date 12/27/2013
------------------------------------	--	---------------------------	------------------------------	----------------------------

TD: 6,318.0

Slant - Original Hole, 1/29/2014 10:38:48 AM



Schematic

Well Name: GMBU B-16-9-16

43-013-51685

SESE 718 FSL 752 FEL Sec 9 T9S R16E Mer SLB

12/18/2013

Rig Release Date
1/2/2014

On Production Date

Original KB Elevation (ft)
5,771APPUWI
43013516850000Well RC
500346804Lease
UTU40894State/Province
UtahField Name
GMBU CTB5County
DuchesneTotal Depth All (TVD) (ftKB)
Original Hole - 6,085.4P81D (AS) (ftKB)
Original Hole - 6,171.0

Most Recent Job

Job Category

Primary Job Type

Secondary Job Type

Job Start Date

Job End Date

Initial Completion

Other Stimulation


P&P

1/21/2014

1/28/2014

TD: 6,226.0

Slant - Original Hole, 2/28/2014 6:22:56 AM



Schematic

Well Name: GMBU S-9-9-16

43-D13-51692

Surface Legal Location

SESE 738 FSL 759 FEL Sec 9 T9S R16E Mer SLB

Spud Date

12/18/2013

Rig Release Date

1/7/2014

On Production Date

Original Hole Elevation (ft)

5,771

Ground Elevation (ft)

5,761

Well RC

500334459

Lease

UTU40894

State/Province

Utah

Field Name

GMBU CTB5

County

Duchesne

Original Hole - 6,186.1

Original Hole - 6,266.7

Most Recent Job

Job Category

Initial Completion

Primary Job Type

Fracture Treatment

Secondary Job Type

P&P

Job Start Date


1/21/2014

Job End Date

1/31/2014

TD: 6,301.0

Slant - Original Hole, 2/28/2014 6:22:06 AM



Multi-Chem Analytical Laboratory

1553 East Highway 40

Vernal, UT 84078

Units of Measurement: **Standard**

Water Analysis Report

Production Company: **NEWFIELD PRODUCTION**Well Name: **STATE 2-16-9-16**Sample Point: **Treater**Sample Date: **7/17/2013**Sample ID: **WA-248308**Sales Rep: **Michael McBride**Lab Tech: **Gary Winegar**Scaling potential predicted using ScaleSoftPitzer from
Brine Chemistry Consortium (Rice University)

Sample Specifics		Analysis @ Properties in Sample Specifics			
		Cations		Anions	
		mg/L		mg/L	
Test Date:	7/24/2013	Sodium (Na):	4413.17	Chloride (Cl):	6000.00
System Temperature 1 (°F):	120	Potassium (K):	55.00	Sulfate (SO ₄):	48.00
System Pressure 1 (psig):	60	Magnesium (Mg):	16.00	Bicarbonate (HCO ₃):	1708.00
System Temperature 2 (°F):	210	Calcium (Ca):	50.00	Carbonate (CO ₃):	
System Pressure 2 (psig):	60	Strontium (Sr):	11.00	Acetic Acid (CH ₃ COO)	
Calculated Density (g/ml):	1.006	Barium (Ba):	47.00	Propionic Acid (C ₂ H ₅ COO)	
pH:	8.70	Iron (Fe):	3.00	Butanoic Acid (C ₃ H ₇ COO)	
Calculated TDS (mg/L):	12357.92	Zinc (Zn):	0.04	Isobutyric Acid ((CH ₃) ₂ CHCOO)	
CO ₂ in Gas (%):		Lead (Pb):	0.20	Fluoride (F):	
Dissolved CO ₂ (mg/L):	0.00	Ammonia NH ₃ :		Bromine (Br):	
H ₂ S in Gas (%):		Manganese (Mn):	0.09	Silica (SiO ₂):	6.42
H ₂ S in Water (mg/L):	5.00				

Notes:

B=8

(PTB = Pounds per Thousand Barrels)

		Calcium Carbonate		Barium Sulfate		Iron Sulfide		Iron Carbonate		Gypsum CaSO ₄ ·2H ₂ O		Celestite SrSO ₄		Halite NaCl		Zinc Sulfide	
Temp (°F)	PSI	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB
210.00	60.00	2.19	43.16	1.32	24.66	3.29	1.65	3.01	2.18	0.00	0.00	0.00	0.00	0.00	0.00	8.16	0.02
200.00	60.00	2.14	43.08	1.34	24.75	3.27	1.65	2.97	2.18	0.00	0.00	0.00	0.00	0.00	0.00	8.25	0.02
190.00	60.00	2.09	42.99	1.36	24.87	3.27	1.65	2.92	2.18	0.00	0.00	0.00	0.00	0.00	0.00	8.34	0.02
180.00	60.00	2.05	42.89	1.38	25.00	3.26	1.65	2.87	2.18	0.00	0.00	0.00	0.00	0.00	0.00	8.43	0.02
170.00	60.00	2.01	42.79	1.41	25.16	3.26	1.65	2.82	2.18	0.00	0.00	0.00	0.00	0.00	0.00	8.54	0.02
160.00	60.00	1.96	42.67	1.44	25.33	3.27	1.65	2.77	2.18	0.00	0.00	0.00	0.00	0.00	0.00	8.65	0.02
150.00	60.00	1.92	42.56	1.48	25.52	3.29	1.65	2.72	2.18	0.00	0.00	0.00	0.00	0.00	0.00	8.77	0.02
140.00	60.00	1.89	42.44	1.52	25.73	3.31	1.65	2.66	2.18	0.00	0.00	0.00	0.00	0.00	0.00	8.90	0.02
130.00	60.00	1.85	42.31	1.57	25.94	3.34	1.65	2.61	2.18	0.00	0.00	0.00	0.00	0.00	0.00	9.03	0.02
120.00	60.00	1.82	42.18	1.63	26.16	3.37	1.65	2.55	2.18	0.00	0.00	0.00	0.00	0.00	0.00	9.18	0.02

Multi-Chem Analytical Laboratory

1553 East Highway 40

Vernal, UT 84078


Water Analysis Report

Temp (°F)	PSI	Hemihydrate CaSO ₄ •0.5H ₂ O		Anhydrate CaSO ₄		Calcium Fluoride		Zinc Carbonate		Lead Sulfide		Mg Silicate		Ca Mg Silicate		Fe Silicate	
		SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB
210.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	1.16	0.02	9.93	0.08	6.80	7.78	3.28	3.97	11.28	2.33
200.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	1.08	0.02	10.08	0.08	6.41	7.78	3.06	3.94	11.02	2.33
190.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	1.00	0.02	10.24	0.08	6.02	7.77	2.83	3.91	10.75	2.33
180.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.91	0.02	10.41	0.08	5.62	7.76	2.60	3.86	10.47	2.33
170.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.82	0.02	10.59	0.08	5.22	7.75	2.38	3.80	10.20	2.33
160.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.73	0.02	10.79	0.08	4.81	7.73	2.15	3.71	9.93	2.33
150.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.63	0.02	10.99	0.08	4.39	7.69	1.91	3.60	9.65	2.33
140.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.52	0.02	11.21	0.08	3.98	7.63	1.68	3.46	9.38	2.33
130.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.40	0.02	11.44	0.08	3.56	7.53	1.45	3.27	9.12	2.33
120.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.29	0.01	11.69	0.08	3.14	7.37	1.22	3.04	8.86	2.33


These scales have positive scaling potential under initial temperature and pressure: Calcium Carbonate Barium Sulfate Iron Sulfide Iron Carbonate Zinc Sulfide Zinc Carbonate Lead Sulfide Mg Silicate Ca Mg Silicate Fe Silicate

These scales have positive scaling potential under final temperature and pressure: Calcium Carbonate Barium Sulfate Iron Sulfide Iron Carbonate Zinc Sulfide Zinc Carbonate Lead Sulfide Mg Silicate Ca Mg Silicate Fe Silicate


Calcium Carbonate




Barium Sulfate



Iron Sulfide




Iron Carbonate




Water Analysis Report


Lead Sulfide




Zinc Sulfide




Ca Mg Silicate



Zinc Carbonate



Mg Silicate




Multi-Chem Analytical Laboratory

1553 East Highway 40

Vernal, UT 84078

Water Analysis Report

Fe Silicate



Multi-Chem Analytical Laboratory

1553 East Highway 40

Vernal, UT 84078

Units of Measurement: **Standard**

Water Analysis Report

Production Company: **NEWFIELD PRODUCTION**Sales Rep: **Michael McBride**Well Name: **SWDIF**Lab Tech: **Gary Peterson**Sample Point: **After Filter**Sample Date: **12/4/2012**Sample ID: **WA-229142**Scaling potential predicted using ScaleSoftPitzer from
Brine Chemistry Consortium (Rice University)

Sample Specifics		Analysis @ Properties in Sample Specifics			
		Cations		Anions	
		mg/L		mg/L	
Test Date:	12/5/2012	Sodium (Na):	734.93	Chloride (Cl):	1000.00
System Temperature 1 (°F):	120.00	Potassium (K):	11.00	Sulfate (SO ₄):	120.00
System Pressure 1 (psig):	60.0000	Magnesium (Mg):	26.00	Bicarbonate (HCO ₃):	366.00
System Temperature 2 (°F):	210.00	Calcium (Ca):	46.20	Carbonate (CO ₃):	
System Pressure 2 (psig):	60.0000	Strontium (Sr):		Acetic Acid (CH ₃ COO)	
Calculated Density (g/ml):	0.999	Barium (Ba):	0.17	Propionic Acid (C ₂ H ₅ COO)	
pH:	6.80	Iron (Fe):	0.13	Butanoic Acid (C ₃ H ₇ COO)	
Calculated TDS (mg/L):	2304.49	Zinc (Zn):	0.02	Isobutyric Acid ((CH ₃) ₂ CHCOO)	
CO ₂ in Gas (%):		Lead (Pb):	0.00	Fluoride (F):	
Dissolved CO ₂ (mg/L):	15.00	Ammonia NH ₃ :		Bromine (Br):	
H ₂ S in Gas (%):		Manganese (Mn):	0.04	Silica (SiO ₂):	
H ₂ S in Water (mg/L):	2.50				

Notes:

9:30

(PTB = Pounds per Thousand Barrels)

		Calcium Carbonate		Barium Sulfate		Iron Sulfide		Iron Carbonate		Gypsum CaSO ₄ ·2H ₂ O		Celestite SrSO ₄		Halite NaCl		Zinc Sulfide	
Temp (°F)	PSI	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB
210.00	60.00	0.28	10.64	0.00	0.00	0.20	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.28	0.01
200.00	60.00	0.19	7.48	0.00	0.00	0.13	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.31	0.01
190.00	60.00	0.11	4.25	0.00	0.00	0.07	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.35	0.01
180.00	60.00	0.02	0.97	0.00	0.00	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.39	0.01
170.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.44	0.01
160.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.50	0.01
150.00	60.00	0.00	0.00	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.56	0.01
140.00	60.00	0.00	0.00	0.05	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.64	0.01
130.00	60.00	0.00	0.00	0.10	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.72	0.01
120.00	60.00	0.00	0.00	0.15	0.03	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.80	0.01


Water Analysis Report

Temp (°F)	PSI	Hemihydrate CaSO ₄ ·0.5H ₂ O		Anhydrate CaSO ₄		Calcium Fluoride		Zinc Carbonate		Lead Sulfide		Mg Silicate		Ca Mg Silicate		Fe Silicate	
		SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB	SI	PTB
210.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
190.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
180.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
170.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
160.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
150.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
140.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
130.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
120.00	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00


These scales have positive scaling potential under initial temperature and pressure: Calcium Carbonate Iron Sulfide Zinc Sulfide

These scales have positive scaling potential under final temperature and pressure: Barium Sulfate Zinc Sulfide


Calcium Carbonate




Barium Sulfate



Iron Sulfide



Zinc Sulfide



Attachment "G"

**State #2-16-9-16
Proposed Maximum Injection Pressure**

Frac Interval (feet)		Avg. Depth (feet)	ISIP (psi)	Calculated Frac Gradient (psi/ft)	Pmax
Top	Bottom				
5546	5556	5551	1642	0.73	1606 ←
4304	5315	4810	2797	1.08	2769
4807	4817	4812	2256	0.90	2225
4718	4725	4722	2000	0.86	1969
				Minimum	<u>1606</u>

Calculation of Maximum Surface Injection Pressure

$$P_{max} = (\text{Frac Grad} - (0.433 \times 1.015)) \times \text{Depth of Top Perf}$$

where pressure gradient for the fresh water is .433 psi/ft and
specific gravity of the injected water is 1.015.

$$\text{Frac Gradient} = (\text{ISIP} + (0.433 \times \text{Top Perf.})) / \text{Top Perf.}$$

Please note: These are existing perforations; additional perforations may be added during the actual conversion procedure.

Daily Activity Report

Format For Sundry

STATE 2-16-9-16

3/1/2008 To 7/30/2008

5/16/2008 Day: 1

Completion

Rigless on 5/15/2008 - Install 5m frac head. NU 6" 5K Cameron BOP. RU H/O truck & pressure test casing, blind rams, frac head, csg & casing valves to 4500 psi. RU Perforators LLC WLT w/ mast & run CBL under pressure. WLTD @ 5735' & cement top @ 54'. Perforate stage #1, CP1 sds @ 5600-07' & 5546-56' w/ 3-1/8" Slick Guns (19 gram, .49"EH, 120°) w/ 4 spf for total of 68 shots. 138 BWTR. SWIFN.

5/22/2008 Day: 2

Completion

Rigless on 5/21/2008 - Stage #1, CP1 sands. RU BJ Services. 0 psi on well. Frac CP1 sds w/ 15,030#'s of 20/40 sand in 274 bbls of Lightning 17 fluid. Broke @ 2435 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 1971 psi @ ave rate of 26.4 BPM. Pumped 504 gals of 15% HCL in flush for Stage #2. ISIP 1642 psi. Leave pressure on well. 412 BWTR Stage #2, LODC sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 11' perf gun. Set plug @ 5400'. Perforate LODC sds @ 5304-15' w/ 3-1/8" Slick Guns w/ 4 spf for total of 44 shots. RU BJ Services. 1281 psi on well. Frac LODC sds w/ 20,640#'s of 20/40 sand in 313 bbls of Lightning 17 fluid. Broke @ 3458 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2881 psi @ ave rate of 23 BPM. Pumped 504 gals of 15% HCL in flush for Stage #3. ISIP 2797 psi. Leave pressure on well. 725 BWTR Stage #3, C sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 10' perf gun. Set plug @ 4910'. Perforate C sds @ 4807-17' w/ 3-1/8" Slick Guns w/ 4 spf for total of 40 shots. RU BJ Services. 1975 psi on well. Frac C sds w/ 24,830#'s of 20/40 sand in 339 bbls of Lightning 17 fluid. Broke @ 2165 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2219 psi @ ave rate of 23 BPM. Pumped 504 gals of 15% HCL in flush for Stage #4. ISIP 2256 psi. Leave pressure on well. 1064 BWTR Stage #4, D2 & D3 sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug, 7' & 7' perf gun. Tagged sand @ 4723'. Unabe to set plug & perforate. POH w/ plug & guns. Flowback well for 3 hrs. Rec 180 BTF. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug, 7' & 7' perf gun. Set plug @ 4785'. Perforate D3 sds @ 4740-47', D2 @ 4718-25' w/ 3-1/8" Slick Guns w/ 4 spf for total of 56 shots. RU BJ Services. 100 psi on well. Started frac. Had trouble w/ chemical truck pumps. SIWFN w/ 884 BWTR.

5/23/2008 Day: 3

Completion

Leed #731 on 5/22/2008 - Day 3. Stage #4, D2 & D3 sands. RU RU BJ Services. 50 psi on well. Frac D2 & D3 sds w/ 25,834#'s of 20/40 sand in 447 bbls of Lightning 17 fluid. Broke @ 2515 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2017 psi @ ave rate of 23.5 BPM. ISIP 2000 psi. Begin immediate flowback on 12/64 choke @ 1 BPM. Flowed for 2 hrs & died. Recovered 120 BTF. MIRU Leed 731. ND Cameron BOP & 5M WH. NU 3M WH & Schaffer BOP. Talley, PU & RIH w/ 4 3/4" Hurricane bit, bit sub & 60 jts of 2 7/8 J-55 tbg. SIWFN w/ 1211 BWTR.

5/24/2008 Day: 4

Completion

Leed #731 on 5/23/2008 - Bleed pressure off well. Rec est 10 BTF. Con't PU & TIH W/ bit and tbg f/ 1920'. Tag fill @ 4670'. Tbg displaced 11 BW on TIH. RU power swivel. C/O sd & drill out composite bridge plugs as follows (using conventional circulation): sd @ 4670', plug @ 4785' in 15 minutes; sd @ 4855', plug @ 4910' in 10 minutes; sd @ 5382', plug @ 5400' in 15 minutes. Con't swivelling jts in hole. Tag fill @ 5676'. Drill plug remains & sd to PBTD @ 5794'. Circ hole clean W/ no fluid loss. RD swivel & pull EOT to 5698'. RU swab equipment. IFL @ sfc. Made 5 swb runs rec 70 BTF W/ light gas & tr oil & sd. FFL @ 1100'. SIFN W/ est 1120 BWTR.

5/28/2008 Day: 5

Completion

Leed #731 on 5/27/2008 - Bleed pressure off annulus--flowing oil. Flow back est 55 BTF (W/ est 25% oil cut & no sand). Circ hole W/ clean wtr. Lost est 30 BW & rec 20 BO. TIH W/ tbg. Tag PBTD @ 5794' (no new fill). LD excess tbg. TOH W/ tbg--LD bit. TIH W/ BHA & production tbg as follows: 2 7/8 NC, 2 jts tbg, SN, 1 jt tbg, new CDI 5 1/2" TA (45K) & 178 jts 2 7/8 8rd 6.5# J-55 tbg. ND BOP. Set TA @ 5558' W/ SN @ 5592' & EOT @ 5655'. Land tbg W/ 15,000# tension. NU wellhead. Flush tbg W/ 60 BW (returned same). PU & TIH W/ pump and rod string to 3100'. PU polished rod & SIFN W/ est 1109 BWTR.

5/29/2008 Day: 6

Completion

Leed #731 on 5/28/2008 - LD polished rod & con't PU "A & "B" grade rod string f/ 3100' (complete as follows): new CDI 2 1/2" X 1 1/2" X 15.5' RHAC pump, 6-1 1/2" weight rods (B), 20-3/4" scraped rods (B), 98-3/4" plain rods (B), 99-3/4" scraped rods (B), 1-8' X 3/4" pony rod (A) and 1 1/2" X 26' polished rod (A). Seat pump & RU pumping unit. Fill tbg W/ 2 BW. Pressure test tbg & pump to 200 psi. Stroke pump up W/ unit to 800 psi. Good pump action. RDMOSU. Est 1111 BWTR. Place well on production @ 3:00 PM 5/28/2008 W/ 56" SL @ 4.5 SPM. FINAL REPORT!!

Pertinent Files: Go to File List

ATTACHMENT H

WORK PROCEDURE FOR PLUGGING AND ABANDONMENT

1. Set CIBP @ 4668'
2. Plug #1 Set 100' plug on top of CIBP using 12 sx Class "G" cement
3. Plug #2 177' balance plug using 21 sx Class "G" cement 50' above Trona-Bird's Nest extending 50' below base of Mahogany Oil Shale
4. Plug #3 120' balance plug using 14sx Class "G" cement 60' above Uinta/Green River and extending 60' below
5. Plug #4 Pump 45 sx Class "G" cement down 5 ½" casing to 374'

The approximate cost to plug and abandon this well is \$42,000.

State 2-16-9-16

Spud Date: 3/31/08

Put on Production: 5/28/08

GL: 5809' KB: 5821'

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts (314.36')

DEPTH LANDED: 324.36'

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sx Class "G", circ. 3 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 141 jts (5817.67')


HOLE SIZE: 7-7/8"

DEPTH LANDED: 5815.67'

CEMENT DATA: 315 sxs Prem, Lite II & 415 sxs 50/50 Poz

CEMENT TOP AT: 54' per CBL 5/15/08

Proposed P & A Wellbore Diagram



State 2-16-9-16
 497' FNL & 1982' FEL
 NW/NE Section 16-T9S-R16E
 Duchesne Co, Utah
 API #43-013-33846; Lease #ML-16532

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-16532
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: 1001 17th Street, Suite 2000 , Denver, CO, 80202		8. WELL NAME and NUMBER: STATE 2-16-9-16
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0497 FNL 1982 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 16 Township: 09.0S Range: 16.0E Meridian: S		9. API NUMBER: 43013338460000
PHONE NUMBER: 303 382-4443 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: DUCHESNE		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/30/2013	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

 Newfield Production proposes to convert the above mentioned well from a producing oil well to an injection well. See attached proposed wellbore diagram.

Accepted by the
 Utah Division of
 Oil, Gas and Mining
FOR RECORD ONLY
 January 08, 2014

NAME (PLEASE PRINT) Jill L Loyle	PHONE NUMBER 303 383-4135	TITLE Regulatory Technician
SIGNATURE N/A	DATE 12/17/2013	

State 2-16-9-16

Spud Date: 3/31/08

Put on Production: 5/28/08

GL: 5809' KB: 5821'

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts (314.36')

DEPTH LANDED: 324.36'

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sx Class "G", circ. 3 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 141 jts (5817.67')

HOLE SIZE: 7-7/8"

DEPTH LANDED: 5815.67'

CEMENT DATA: 315 sxs Prem. Lite II & 415 sxs 50/50 Poz

CEMENT TOP AT: 54' per CBL 5/15/08

TUBING (GI 4/5/11)

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#

NO. OF JOINTS: 178 jts (5548.8')

TUBING ANCHOR: 5560.8'

NO. OF JOINTS: 1 jt (31.5')

SEATING NIPPLE: 2-7/8" (1.10')


SN LANDED AT: 5595.1' KB

NO. OF JOINTS: 2 jts (62.1')

NOTCHED COLLAR: 2-7/8" (0.5')

TOTAL STRING LENGTH: EOT @ 5659' KB

Proposed Injection Wellbore Diagram



FRAC JOB

05-21-08 5546-5556' **Frac CP1 sds as follows:**
15,030# 20/40 sand in 274 bbls of Lightning 17 fluid. Treated w/ ave
pressure of 1971 psi @ ave rate of 26.4 BPM. ISIP 1642 psi. Actual
Flush: 5040 gals.

05-21-08 5304-5315' **Frac LODC sds as follows:**
20,640# 20/40 sand in 313 bbls of Lightning 17 fluid. Treated w/ ave
pressure of 2881 psi @ ave rate of 23 BPM. ISIP 2797 psi. Actual
Flush: 4801 gals.

05-21-08 4807-4817' **Frac C sds as follows:**
24,830# 20/40 sand in 339 bbls of Lightning 17 fluid. Treated w/ ave
pressure of 2219 psi @ ave rate of 23 BPM. ISIP 2256 psi. Actual
Flush: 4330 gals.

05-22-08 4718-4725' **Frac D2 & D3 sds as follows:**
25,834# 20/40 sand in 447 bbls of Lightning 17 fluid. Treated w/ ave
pressure of 2017 psi @ ave rate of 23.5 BPM. ISIP 2000 psi. Actual
flush: 4670 gals.

2/18/09 Tubing Leak. Updated r & t details.

4/7/11 Tubing leak. Updated Rod & tubing details.

PERFORATION RECORD


4718-4725'	4 JSPF	28 holes
4740-4747'	4 JSPF	28 holes
4807-4817'	4 JSPF	40 holes
5304-5315'	4 JSPF	44 holes
5546-5556'	4 JSPF	40 holes
5600-5607'	4 JSPF	28 holes



State 2-16-9-16
497' FNL & 1982' FEL
NW/NE Section 16-T9S-R16E
Duchesne Co, Utah
API #43-013-33846; Lease #ML-16532

JL 11/25/2013

RECEIVED: Dec. 17, 2013

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-16532			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)			
1. TYPE OF WELL Water Injection Well	8. WELL NAME and NUMBER: STATE 2-16-9-16				
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY	9. API NUMBER: 43013338460000				
3. ADDRESS OF OPERATOR: Rt 3 Box 3630, Myton, UT, 84052	PHONE NUMBER: 435 646-4825 Ext	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0497 FNL 1982 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 16 Township: 09.0S Range: 16.0E Meridian: S	COUNTY: DUCHESNE STATE: UTAH				
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 4/4/2014 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between; align-items: flex-start;"> <div style="width: 60%;"> <p>The above reference well was put on injection at 1:30 PM on 04/04/2014.</p> </div> <div style="width: 35%; text-align: right;"> <p>Accepted by the Utah Division of Oil, Gas and Mining</p> <p>Date: April 21, 2014</p> <p>By: </p> </div> </div>					
NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician			
SIGNATURE N/A	DATE 4/8/2014				

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-16532
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630, Myton, UT, 84052		8. WELL NAME and NUMBER: STATE 2-16-9-16
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0497 FNL 1982 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 16 Township: 09.0S Range: 16.0E Meridian: S		9. API NUMBER: 43013338460000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: DUCHESNE		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 3/14/2014			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The subject well has been converted from a producing oil well to an injection well on 03/13/2014. On 03/13/2014 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 03/14/2014 the casing was pressured up to 1449 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 0 psig during the test. There was not a State representative available to witness the test.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

Date: April 02, 2014
By:

NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician
SIGNATURE N/A	DATE 3/31/2014	

Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company
Rt. 3 Box 3630
Myton, UT 84052
435-646-3721

Witness: _____ Date 3/14/14 Time 12:42 am ☒ pm

Test Conducted by: Ricky Bessly

Others Present: _____

Well: <u>State 2-16-9-16</u>	Field: <u>monument 130 ft</u>
Well Location: <u>State 2-16-9-16</u> <u>NW/NE Sec. 16, T9S, R16E</u> <u>Duchesne County Utah</u>	API No: <u>4301333846</u>

<u>Time</u>	<u>Casing Pressure</u>	
0 min	<u>1453</u>	psig
5	<u>1452</u>	psig
10	<u>1451</u>	psig
15	<u>1451</u>	psig
20	<u>1450</u>	psig
25	<u>1450</u>	psig
30 min	<u>1449</u>	psig
35	_____	psig
40	_____	psig
45	_____	psig
50	_____	psig
55	_____	psig
60 min	_____	psig

Tubing pressure: 0 psig


Result: Pass Fail

Signature of Witness: _____

Signature of Person Conducting Test: Ricky Bessly

State 2-16-9-16 (conversion MIT 3-14-14)

3/14/2014 12:42:05 PM





Job Detail Summary Report

Well Name: State 2-16-9-16

Jobs

Primary Job Type Conversion	Job Start Date 3/11/2014	Job End Date
--------------------------------	-----------------------------	--------------

Daily Operations

Report Start Date	Report End Date	24hr Activity Summary
3/11/2014	3/11/2014	RD MOVE RIG FROM 14-29-8-17 TO 2-16-9-16
Start Time	End Time	Comment
06:00	07:00	CREW TRAVEL TO LOCATION
Start Time	End Time	Comment
07:00	07:30	SAFETY MEETING (GOOD COMMUNICATION) PREP FOR RIG DOWN
Start Time	End Time	Comment
07:30	08:30	RIG DOWN LOAD EQUIPMENT, PREP EQUIPMENT TO MOVE TO STATE 2-16-9-16
Start Time	End Time	Comment
08:30	09:30	MOVE RIG TO LOCATION (STATE 2-16-9-16)
Start Time	End Time	Comment
09:30	10:30	SPOT IN EQUIPMENT, LEVEL UP RIG, RIG SERVICE GREASE CROWN, BLOCKS, DRIVELINES)
Start Time	End Time	Comment
10:30	15:00	WAIT ON WIND. TO WINDY TO RIG UP SHUT DOWN DUE TO WIND
Start Time	End Time	Comment
15:00	16:00	CREW TRAVEL HOME
Report Start Date	Report End Date	24hr Activity Summary
3/12/2014	3/12/2014	LD RODS, FLUSH. ND WH, UNSEAT ANCHOR
Start Time	End Time	Comment
06:00	07:00	CREW TRAVEL TO LOC
Start Time	End Time	Comment
07:00	08:00	RIG UP AND REMIVE HORSES HEAD
Start Time	End Time	Comment
08:00	08:30	SWITCH 400 BBLs TANKS, BLEED DOWN WELL SICP 100 PSI SITP - 25 PSI
Start Time	End Time	Comment
08:30	09:00	LAY DOWN 1 1/2" POLISH ROD, 2 - 3/4" X 2' PONYS, 2 - 3/4" X 8' PONYS, 2 - 3/4" 4 PERS
Start Time	End Time	Comment
09:00	10:00	FLUSH 2 7/8" J-55 TUBING WITH 30 BBLs @ 250 DEGREES
Start Time	End Time	Comment
10:00	10:30	PICK UP 2 - 3/4" 4 PER, 2 - 3/4" 8' PONY SUBS, 1 - 3/4" 4 PER SOFTT SEAT PUMP. REMOVE B-1 FLOW TEE AND FILL 2 7/8" TUBING WIT 10 BLS. PRESSURE TEST TO 3400 PSI GOOD TEST. LAY DOW 1 - 3/4" 4 PER FOR RIG, 2 - 3/4" 8' PONY SUBS
Start Time	End Time	Comment
10:30	12:00	LAY DOWN 3/4" RODS ONTO TRAILER. 93 - 4 PER GOOD, 3- 4 PER BAD (96 TOTAL), 36- 3/4" SLICKS GOOD, 3- 3/4" SLICKS BAD. FLUSH WITH 20 BBLs @ 250 DEGREES
Start Time	End Time	Comment
12:00	13:00	LAY DOWN 3/4" RODS ONTO TRAILER. 16- 3/4" SLICKS GOOD, 13- 3/4" BAD, (52 GOOD) (16 BAD) (68 TOTAL SLICKS), 51 - 3/4" 8 PER, 6 - 1 1/2" SINKER BARS, 6 - 1" STABILIZER, 1 PUMP 2 1/2"x1 1/4"x14'x16' RHAC CD!
Start Time	End Time	Comment
13:00	14:00	CHANGE OVER BLOCK, NIPPLE DOWN WELL HEAD, UNSET ANCHOR, NIPPLE UP BOP'S, (FUNCTION TEST PIPE RAMS) RIG UP FLOOR, 2 SETS TONGS
Start Time	End Time	Comment
14:00	15:30	R/U SANDLINE, RUN IN HOLE W/ SANDLINE F/ TAG, TUBING WAXY, FLUSH 2 7/8" J-55 TBG W/20 BBLs @ 250 DEGREES, TAG @ 5779. 15' OF FILL. PULL OUT OF HOLE, RIG DOWN SANDLINE
Start Time	End Time	Comment
15:30	18:00	PULL OUT OF TO DERRICK WITH 2 7/8" J-55 TUBING, BREAK, DOPE, AND MAKE UP COLLARS 60 JOINTS IN DERRICK. TALLEY DEPTH 1864.19'
Start Time	End Time	Comment
18:00	19:00	CREW TRAVEL



Job Detail Summary Report

Well Name: State 2-16-9-16

Daily Operations

Report Start Date	Report End Date	24hr Activity Summary
3/13/2014	3/13/2014	TOOH W/ TBG, BREAK, DOPE & M/U COLLARS
Start Time	End Time	Comment
06:00	07:00	CREW TRAVEL TO LOCATION
Start Time	End Time	Comment
07:00	07:30	SAFETY MEETING, SICP 50 PSI, SITP 25 PSI, BLEED OFF, FLUSH 2 7/8" J-55 TUBING WITH 20 BBLS @ 250 DEGREES
Start Time	End Time	Comment
07:30	08:30	WORK ON RIG AIR PROBLEMS.
Start Time	End Time	Comment
08:30	12:00	PULL TUBING OUT OF HOLE TO DERRICK, BREAK, DOPE, AND MAKE UP COLLARS (TALLEY) 90 JOINTS DEPTH 2798.78 (TOTAL 150 JOINTS = 4662.97)
Start Time	End Time	Comment
12:00	13:00	FLUSH INSIDE OF 2 7/8" J-55 TUBING WITH 20 BBL , LAY DOWN 31 JOINTS ONTO TRAILER, ANCHOR, 2 7/8" SEAT NIPPLE, BLEED NIPPLE, AND NOTCH COLLAR
Start Time	End Time	Comment
13:00	14:30	M/U 2 3/8" XN NIPPLE, PUP SUB, 2 3/8" X 2 7/8" XO, 5 1/2" X 2 7/8" PKR, ON/OFF TOOL, 2 7/8" SEAT NIPPLE, RUN 150 JOINTS 2 7/8" J-55 TUBING F/ DERRICK, ADDED 8' PUP JOINT.
Start Time	End Time	Comment
14:30	15:00	FLUSH WITH 15 BBLS, DROP STAND VALVE, FILL 2 7/8" TUBING W/ 20 BBLS AND PRESSURE TEST TO 3000 PSI
Start Time	End Time	Comment
15:00	18:30	PRESSURE BLED DOWN, BUMPED UP TO PRESSURE OF 3000 PSI 13 TIMES. HELD 3000 PSI FOR 30 MINUTES. GOOD TEST
Start Time	End Time	Comment
18:30	19:30	R/U LUB.
Report Start Date	Report End Date	24hr Activity Summary
3/14/2014	3/14/2014	SET PKR, ND BOPS, NU WH
Start Time	End Time	Comment
06:00	07:00	CREW TRAVEL
Start Time	End Time	Comment
07:00	08:30	SAFETY MEETING (RIGGING DOWN), SITP- 25 PSI, SICP- 25 PSI, BLEED DOWN TUBING AND CASING. RIG DOWN FLOOR, NIPPLE DOWN BOP'S, SET PACKER @ 4664.07 WITH 15,000# TENSION, NIPPLE UP WELL HEAD.
Start Time	End Time	Comment
08:30	10:30	FILL CASING WITH 35 BBLS, PRESSURE UP TO 1,500 PSI. PRESSURE UP 3 TIMES LOST PRESSURE 1ST 200 PSI IN 20 MINUTE, 2ND- 150 PSI IN 20 MINUTE, 3RD- 50 PSI IN 20 MINUTE, HELD PRESSURE FOR 30 MINUTE
Start Time	End Time	Comment
10:30	11:00	CALL FOR PUMPER TO DO MIT TEST. WAIT ON PUMPER
Start Time	End Time	Comment
11:00	11:30	RIG UP PUMPER F/ MIT TEST. DID MIT TEST, DIDN'T TEST. WAIT 1 HR TO RETEST
Start Time	End Time	Comment
11:30	12:30	WAITING TO RETEST MIT



Job Detail Summary Report

Well Name: State 2-16-9-16

--

Start Time	12:30	End Time	13:00	Comment
				START MIT TEST #2. GOOD TEST, RIG DOWN PUMPER. On 03/13/2014 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 03/14/2014 the casing was pressured up to 1449 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 0 psig during the test. There was not a State representative available to witness the test.
Start Time	13:00	End Time	14:30	Comment
				CHANGE OVER BLOCKS, RIG DOWN, PREP TO MOVE RIG WELL SHUT IN. LEFT LOC FINAL REPORT

--

NEWFIELD**Schematic****Well Name: State 2-16-9-16**

Surface Legal Location 16-9S-16E			API/UWI 43013338460000	Well RC 500218527	Lease	State/Province Utah	Field Name GMBU CTB5	County DUCHESNE
Spud Date	Rig Release Date	On Production Date 5/28/2008	Original KB Elevation (ft)	Ground Elevation (ft)	Total Depth All (TVD) (ftKB)		PBTD (All) (ftKB)	

Most Recent Job

Job Category Production / Workover	Primary Job Type Conversion	Secondary Job Type Basic	Job Start Date 3/11/2014	Job End Date
---------------------------------------	--------------------------------	-----------------------------	-----------------------------	--------------

TD: 5,815.7

Vertical - Original Hole, 3/26/2014 10:00:37 AM

MD (ftKB)	TVD (ftKB)	Incl (°)	DLS	DLS (°...)	Vertical schematic (actual)
0.3					<p>1; Surface; 8 5/8 in; 8.097 in; 12-324 ftKB; 312.36 ft</p> <p>6-1; Tubing; 2 7/8; 2.441; 0-4,663; 4,662.97</p> <p>6-2; Seat Nipple; 2 7/8; 2.441; 4,663-4,664; 1.10</p> <p>6-3; On-Off Tool; 2 7/8; 2.441; 4,664-4,666; 1.90</p> <p>6-4; Packer; 5 1/2; 4.950; 4,666-4,673; 6.94</p> <p>6-5; Cross Over; 2 3/8; 1.991; 4,673-4,674; 0.50</p> <p>6-6; Tubing Pup Joint; 2 3/8; 1.991; 4,674-4,678; 4.50</p> <p>6-7; XN Nipple; 2 3/8; 1.991; 4,678-4,679; 1.20</p> <p>Perforated; 4,718-4,725; 5/21/2008</p> <p>Perforated; 4,740-4,747; 5/21/2008</p> <p>Perforated; 4,807-4,817; 5/21/2008</p> <p>Perforated; 5,304-5,315; 5/21/2008</p> <p>Perforated; 5,546-5,556; 5/15/2008</p> <p>Perforated; 5,600-5,607; 5/15/2008</p> <p>2; Production; 5 1/2 in; 4.950 in; 12-5,816 ftKB; 5,803.67 ft</p>
12.1					
323.5					
324.5					
3,000.0					
4,663.1					
4,664.4					
4,666.0					
4,673.2					
4,673.6					
4,678.1					
4,679.5					
4,717.8					
4,725.1					
4,740.2					
4,747.0					
4,807.1					
4,816.9					
5,304.1					
5,315.0					
5,545.9					
5,556.1					
5,600.1					
5,607.0					
5,794.9					
5,815.0					
5,815.6					

NEWFIELD**Newfield Wellbore Diagram Data****State 2-16-9-16**

Surface Legal Location 16-9S-16E			API/UWI 43013338460000		Lease	
County DUCHESE		State/Province Utah		Basin		Field Name GMBU CTB5
Well Start Date		Spud Date		Final Rig Release Date		On Production Date 5/28/2008
Original KB Elevation (ft)	Ground Elevation (ft)	Total Depth (ftKB) 5,815.7		Total Depth All (TVD) (ftKB)		PBTD (All) (ftKB)

Casing Strings

Csg Des	Run Date	OD (in)	ID (in)	Wt/Len (lb/ft)	Grade	Set Depth (ftKB)
Surface	3/31/2008	8 5/8	8.097	24.00	J-55	324
Production	4/29/2008	5 1/2	4.950	15.50	J-55	5,816

Cement**String: Surface, 324ftKB 4/3/2008**

Cementing Company		Top Depth (ftKB) 12.0	Bottom Depth (ftKB) 324.4	Full Return?	Vol Cement Ret (bbl)	
Fluid Description Class "G" w/ 2% CaCL2 + 1/4#/sk Cello-Flake mixed @ 15.8 ppg 1.17 cf/sk yield		Fluid Type Lead	Amount (sacks) 160	Class G	Estimated Top (ftKB) 12.0	

String: Production, 5,816ftKB 4/30/2008

Cementing Company		Top Depth (ftKB) 12.0	Bottom Depth (ftKB) 3,000.0	Full Return?	Vol Cement Ret (bbl)	
Fluid Description Premilite II w/ 10% gel + 3% KCL, 3#s /sk CSE + 2# sk/kolseal + 1/2#s/sk Cello Flake mixed @ 11.0 ppg W / 3.43 cf/sk yield		Fluid Type Lead	Amount (sacks) 300	Class PLII	Estimated Top (ftKB) 12.0	

String: Production, 5,816ftKB 4/30/2008

Cementing Company		Top Depth (ftKB) 3,000.0	Bottom Depth (ftKB) 5,815.7	Full Return?	Vol Cement Ret (bbl)	
Fluid Description 50/50 poz W/ 2% Gel + 3% KCL, .5%EC1, 1/4# sk C.F. 2% gel. 3% SM mixed @ 14.4 ppg W/ 1.24 YLD		Fluid Type Tail	Amount (sacks) 400	Class 50/50	Estimated Top (ftKB) 3,000.0	

Tubing Strings

Tubing Description Tubing				Run Date 3/12/2014		Set Depth (ftKB) 4,679.3		
Item Des	Jts	OD (in)	ID (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)
Tubing	150	2 7/8	2.441	6.50	J-55	4,662.97	0.2	4,663.2
Seat Nipple		2 7/8	2.441			1.10	4,663.2	4,664.3
On-Off Tool		2 7/8	2.441			1.90	4,664.3	4,666.2
Packer		5 1/2	4.950			6.94	4,666.2	4,673.1
Cross Over		2 3/8	1.991			0.50	4,673.1	4,673.6
Tubing Pup Joint		2 3/8	1.991			4.50	4,673.6	4,678.1
XN Nipple		2 3/8	1.991			1.20	4,678.1	4,679.3

Rod Strings

Rod Description				Run Date		Set Depth (ftKB)		
Item Des	Jts	OD (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)	

Perforation Intervals

Stage#	Zone	Top (ftKB)	Btm (ftKB)	Shot Dens (shots/ft)	Phasing (*)	Nom Hole Dia (in)	Date
4	D2, Original Hole	4,718	4,725	4			5/21/2008
4	D3, Original Hole	4,740	4,747	4			5/21/2008
3	C, Original Hole	4,807	4,817	4			5/21/2008
2	LODC, Original Hole	5,304	5,315	4			5/21/2008
1	CP1, Original Hole	5,546	5,556	4		0.490	5/15/2008
1	CP1, Original Hole	5,600	5,607	4		0.490	5/15/2008

Stimulations & Treatments

Stage#	ISIP (psi)	Frac Gradient (psi/ft)	Max Rate (bbl/min)	Max PSI (psi)	Total Clean Vol (bbl)	Total Slurry Vol (bbl)	Vol Recov (bbl)
1	1,642	0.73	26.7	2,188			
1	1,642	0.73	26.7	2,188			
2	2,797	0.96	23.1	3,035			
3	2,256	0.9	23.1	2,389			
4	2,000	0.86	24.0	2,272			
4	2,000	0.86	24.0	2,272			